

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-22482-01-00  
Spot: SENESE Sec/Twnshp/Rge: 21-24S-33W  
2125 feet from S Section Line, 185 feet from E Section Line  
Lease Name: MCWILLIAMS E Well #: 6  
County: FINNEY Total Vertical Depth: 1288 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY, LLC  
Address: 13727 NOEL ROAD, SUITE 1200  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	0	0	0	

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2018 1:30 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: RODNEY GONZALEZ Company: MERIT ENERGY Phone: (972) 628-1558

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: SCOTT ALBERG WitnessType: NONE  
Date/Time Plugging Completed: 03/31/2018 11:30 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

Perfs:

LEFT IN HOLE 18 61/4" COLLARS WITH 12" REAMER, 12 1/4" PDC BIT & 5 JOINTS DRILLING PIPE. TOP OF FISH 564'. FILL FROM 564' TO SURFACE. ALSO LEFT APPROXIMATELY 200' 7 5/8" WASHOVER PIPE. ESTIMATED TOP OF WASHOVER PIPE FISH AT 460'. RAN DRILL PIPE TO 564' (INSIDE WASHOVER PIPE) PUMPED 400 SX 60/40 POZMIX 4% GEL 1/4% FLO SEAL. PUMP 30 SX CMT IN RATHOLE. PUMP 20 SX CMT IN MOUSEHOLE. TOP OFF WELL WITH 50 SX COMMON CEMENT WITH 1% CC.

Remarks: USED 60/40 POZMIX 4% GEL BY BJ

Plugged through: DP

INVOICED  
APR 26 2018

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
APR - 9 2018  
KCC DODGE CITY