

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-22719-00-00
Spot: S2N2S2SE Sec/Twnshp/Rge: 29-15S-13W
825 feet from S Section Line, 1320 feet from E Section Line
Lease Name: SELLENS Well #: 2
County: RUSSELL Total Vertical Depth: 3326 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3326		150 SX
SURF	8.625	361		210 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2018 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL, INC. DBA Phone: (620) 938-2943

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls and 8 sx gel.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2018 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1450', 900' and 350'. Ran tubing to 3200' and pumped 8 sx gel followed by 75 sx cement w/100 # hulls. Pulled tubing to 1450' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 500' and pumped 70 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 90 sx cement. Circulated cement out of braden head to the pit.

GPS: 38.71357 -098.78705

Perfs:

Top	Bot	Thru	Comments
3326	3328		

KCC WICHITA
MAR 16 2018
RECEIVED

INVOICED
APR 26 2018

Remarks: COPELAND ACID AND CEMENTING TICKET # 31529

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

FEB 20 2018