

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-20406-00-00
Spot: W2E2 Sec/Twnshp/Rge: 5-26S-17W
2666 feet from S Section Line, 1978 feet from E Section Line
Lease Name: ROENBAUGH JAKE Well #: 1-5
County: EDWARDS Total Vertical Depth: 4634 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4550		WITH 2 SX CMT
PROD	4.5	4626	1735	WITH 200 SX CMT
SURF	8.625	501		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/20/2018 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING Phone: (800) 433-9047

Proposed Plugging Method: CIBP AT 4450' WITH 2 SX CMT. PLUG AT 1200' WITH 12 SX GEL & 50 SX CMT. PLUG AT 530' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/21/2018 10:00 AM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4550' WITH 2 SX CMT. 1ST PLUG AT 1200' WITH 12 SX GEL & 50 SX CMT. GOT FLUID RETURNS TO SURFACE AT END OF DISPLACEMENT OF PLUG. 2ND PLUG PULL CASING TO 530' & PUMP 50 SX CMT. NO FLUID RETURN TO SURFACE. 3RD PLUG PULL CASING TO 40' & PUMP 100 SX CMT WITHOUT RETURNS TO SURFACE. SDON. 3/21/18: RUN IN WITH SAND LINE & TAG CMT PLUG AT 250'. FILL HOLE WITH 40 SX CMT. CMT REMAINING AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
4546	4550		
4538	4540		
4528	4529		
4521	4522		
4502	4505		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENTING.

INVOICED
APR 26 2018

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
MAR 26 2018
KCC DODGE CITY