

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-22613-00-00
Spot: NWNWSENE Sec/Twnshp/Rge: 22-28S-9E
3807 feet from S Section Line, 1122 feet from E Section Line
Lease Name: KNOX Well #: 1-22
County: ELK Total Vertical Depth: 2946 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2942		330 SX
SURF	8.625	52		55 SX
T1	2.375	2792		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/17/2018 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: STAN FROETSCHNER Company: _____ Phone: (800) 433-9047

Proposed Plugging Method: As directed by the KCC.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 01/17/2018 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

1/17/18 Rig up HSI Cmt. Hook up to 2 3/8" tbg, @ 2845' pump 18 bbls H2O to break circ. mix & pump 30 Bbls gel. 25 sks 60/40 poz. w/ 4% gel. & 40# hulls, displace down w/ 10 Bbls H2O, pull tbg to 1300', mix & pump 18 Bbls gel, 25 sks 60/40 poz/ w/ 4% gel, displace down w/ 3 Bbls H2O, pull tbg to 490', mix & pump 55 sks cmt, circ to cmt to pit, pull tbg, top off csg w/ 5 sks cmt. 1/30/18 Top off 5 1/2 casing with (7) 80# bags of Quickrete.

Top	Bot	Thru	Comments
2838	2842		

RECEIVED
KCC DIST #3
APR 04 2018
CHANUTE, KS
DS


Remarks:

Plugged through: TBG

INVOICED
APR 26 2018

District: 03

Signed



(TECHNICIAN)