

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-093-20462-00-00
Spot: S2NE Sec/Twnshp/Rge: 2-26S-37W
3300 feet from S Section Line, 1320 feet from E Section Line
Lease Name: TATE Well #: 4
County: KEARNY Total Vertical Depth: 2900 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN LLC
Address: 15 E 5TH ST STE 3300
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2640		
PROD	4.5	2883	0	WITH 750 SX CMT
SURF	8.625	610		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/31/2018 10:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: _____ Phone: (918) 583-3333

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/31/2018 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2640' WITH 20' BAILER FILLED WITH 2 SX CMT STUCK & LEFT IN HOLE. FILL THE CASING WITH CMT FROM 2640' TO 0' USING 160 SX CMT. PRESSURED TO 500#. HOLDING. FILL THE ANNULUS WITH 40 SX CMT. PRESSURE TO 200#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2694	2770		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

INVOICED
APR 26 2018

District: 01

Signed *Ken Jehlik*
(TECHNICIAN)
SK

RECEIVED
FEB 12 2018
KCC DODGE CITY *MR*