

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-10256-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 22-22S-22W
639 feet from S Section Line, 3260 feet from E Section Line
Lease Name: MILLER ARTHUR Well #: 3
County: HODGEMAN Total Vertical Depth: 4442 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: PO BOX 559
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		630		WITH 2 SX CMT
CIBP		4260		WITH 2 SX CMT
PROD	5.5	4413	0	WITH 125 SX CMT
SURF	8.625	250		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2018 9:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: DICK SCHREMMER Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 523-1225

Proposed Plugging Method: PERFORATE AT 1370' SET RETAINER AT 1200' & PUMP 50 SX CMT, 25 SX WITHOUT HULLS & 25 SX WITH HULLS. SET CIBP @ 650'. PERFORATE AT 550' & PUMP 80 SX CMT OVER CASING VOLUME. IF DOESN'T CIRCULATE PUMP 100 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2018 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

TRIED TO RUN PERFORATING TOOL TO 1370'. COULDN'T GET PAST 825'. PULLED TOOL OUT OF HOLE & RAN TBG. HAD TO WORK IT & FINALLY GOT IT TO 1398'. PUMPED 80 SX CMT. PULLED TBG. RAN CIBP TO 630' & PUT 2 SX CMT ON IT. PERFORATED AT 550' & TIED ONTO CASING & PUMPED 180 SX CMT. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 325# & HELD. WELL WAS FLOWING UNTIL WE SET THE CIBP @ 630'. IT HAD A CEDAR HILLS BREAK-IN.

Perfs:

Top	Bot	Thru	Comments
4413	4442	OH	
4370	4380	CSG	

INVOICED
APR 27 2018

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENTING.

Plugged through: TBG

District: 01

Signed

Michael Maier

(TECHNICIAN)

518

RECEIVED
FEB 20 2018
KCC DODGE CITY

MR