

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-21632-00-00  
Spot: E2SWSESE Sec/Twnshp/Rge: 17-22S-8W  
660 feet from S Section Line, 710 feet from E Section Line  
Lease Name: ZWICK Well #: 1  
County: RENO Total Vertical Depth: 3647 feet

Operator License No.: 31714  
Op Name: NOVY OIL & GAS, INC.  
Address: PO BOX 559  
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3648	2285	150 SX
SURF	8.625	265		225 SX
T1	2.875	3615		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/23/2017 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: \_\_\_\_\_ Phone: (620) 282-2212

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/24/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SANDED BACK TO 3350'- CAPPED WITH 5 SX CEMENT. CUT CASING OFF QT 2285' - PULLED TO 1310' SPOTTED 50 SX COMMON 3% CC. WAITED 1.5 HOURS AND TAG PLUG AT 1050'. SPOTTED 35 SX COMMON 3% CC AT 700'. CIRCULATED TO SURFACE FROM 310' WITH 180 SX 60/40 POZ 4% CEMENT.

Top	Bot	Thru	Comments
3562	3580		

Remarks: TICKET #45579 COPELAND CEMENTING, JUNK IN HOLE COULD NOT TA. DENIED TA

Plugged through: CSG

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)