


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Basing Building
Wichita, Kansas

Barton County, Sec. 4 Twp. 20 Rge. 12 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NW SW NE
Lease Owner W. J. Coppinger et al
Lease Name Wearne Well No. 1
Office Address 320 Union Natl Bk Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed (As producer in June 1951) 19
Application for plugging filed August 12 1953
Application for plugging approved August 12 1953
Plugging commenced August 17 1953
Plugging completed August 21 1953
Reason for abandonment of well or producing formation Production no longer commercial
If a producing well is abandoned, date of last production Feb. 28 1953
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Charlie Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3402 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand to 3370'. Dumped 5 sacks of cement there.
Shot pipe off at 2520'. Pulled pipe and pumped 30 sax of mud with Halliburton. Set Halliburton plug and pumped 100 sax of cement in with Halliburton.

RECEIVED
STATE CORPORATION COMMISSION
SEP - 2 1953
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bert Self
Address R R #4 - Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. J. Coppinger (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Coppinger
320 Union Natl Bk Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 19 53
Maycee Broadman
Notary Public.

My commission expires March 7, 1956

PLUGGING
FILE SEC 4 T 20 R 12
BOOK PAGE 121 LINE 19


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - W. J. COPPINGER et al
Farm - Wearne No. 1

SEC. 4 T. 20 R. 12W
NW SW NE

Total Depth. 3402
Comm. 5-10-51 Comp. 5-25-51
Shot or Treated.
Contractor.
Issued. 9-1-51

County. Barton
KANSAS



CASING:
8 5/8" 222' cem. w/135 sx
5 1/2" 3386' cem. w/75 sx

Elevation. 1815 DF

Production. 3 BOPH

Figures Indicate Bottom of Formations.

sand	60
clay	100
limestone	120
iron	126
shale & shells	220
clay	290
red bed	450
anhydrite	650
shale	840
shale & shells	1280
shale & lime	1510
lime	1630
lime & shale	1705
lime	1840
lime & shale	2280
shale	2385
shale & lime	2865
lime	2929
lime & shale	3043
shale	3130
lime & shale	3295
lime	3245
lime & shale	3278
lime	3365
lime & shale	3384
arbuckle	3390 RTD
arbuckle	3402
Total Depth	

Tops:

Anhydrite	620
Heebner	2998
Lansing	3135
Arbuckle	3384

Swab 3 BOPH 28 hours

PLUGGING
FILE SEC 4 T 20 R 12W
BOOK PAGE 121 LINE 19

RECEIVED
OCT 10 1951