

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Barton County. Sec. 4 Twp. 20S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines NE SE SW  
Lease Owner Circle Oil Company, Inc.  
Lease Name Tonkin Well No. 1  
Office Address 500 Bitting Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Oct. 15, 19 71  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced Oct. 15, 19 71  
Plugging completed Oct. 15, 19 71  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plot

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Don Truan of Russell)

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3456 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: Surface, 0, 219', 8-5/8", 219', ----. Row 2: Casing

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from Total Depth to 480 Feet,  
Plug and 40 sax cement; Mud to  
220', Plug and 25 sax cement;  
Mud to 40', 1/2 sax hulls, plug and  
10 sax cement to base of cellar;  
2 sax cement in Rat Hole. Job  
completed @ 1:45 P.M. by Allied.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co.  
Address Box 207, Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Clarence Michael of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael  
500 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 71

Louise K. Whitted  
Louise K. Whitted - Notary Public.

My commission expires November 26, 1974.



DRILLERS LOG

TONKIN NO. 1

CASING RECORD:	OPERATOR: Circle Oil Company, Inc.	DESCRIPTION:
8-5/8" @ 219'	CONTRACTOR: Sage Drilling Co., Inc.	NE SE SW
w/160 sax cement	COMMENCED: October 1, 1971	Sec. 4-20S-12W
TOTAL DEPTH:	COMPLETED: October 15, 1971	Barton Co., Kansas
3456'		ELEVATION: 1816KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	150	
Shale	150	223	
Red Bed	223	620	
Anhydrite	620	647	
Shale	647	1440	
Lime & Shale	1440	3140	
Lime	3140	3290	
Lime & Shale	3290	3298	
Lime	3298	3456	D&A

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael  
Clarence Michael



Subscribed and sworn to before me this 18th day of October, 1971.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1974.