

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County, Sec. 5 Twp. 20 Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SE SE

Lease Owner B. E. Ash

Lease Name Lanterman

Well No. C-2

Office Address Box 211, Ellinwood, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 1-29 19 57

Application for plugging filed 1-29 19 57

Application for plugging approved 1-29 19 57

Plugging commenced 1-29 19 57


Plugging completed 1-29 19 57

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? (Mr. Brundage)



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Arbuckle

Depth to top 3418 Bottom 3438

Total Depth of Well 3485 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	200	8 5/8	200	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dry and abandoned - Plugged 1-29-57 Plugging bottom plug 185' - Dumped 1/3 sack hulls. Dumped 20 sacks cement. Top plug @ 35'. Dumped 1/3 sack hulls. Dumped 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bea Drilling Company
Address Box 211, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
B. E. ASH (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

B. E. Ash
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of February, 19 57

My commission expires 4-27-57

Notary Public.

PLUGGING
FILE SEC 5 T. 20 R. 12 W
BOOK PAGE 157 LINE 16

Well Log
Lanterman C-2
NW SE SE Sec 5-T20S-R12W
Barton County, Kansas

0 - 90	Sand and clay	Elevation 1824 D.F.	1826 K.B.
90 - 111	Shale and shells		
111 - 145	Iron and shale		
145 - 170	Shale and shells		
170 - 200	Blue shale	Topeka	2866 - 1040
200 - 720	Red bed	Heebner	3023 - 1193
720 - 750	Anhydrite	Toronto	3046 - 1220
750 - 1170	Red rock and shales	Douglas	3056 - 1230
1170 - 1325	Salt and shells	Brown lime	3138 - 1312
1325 - 1730	Shale and shells	Lansing Kansas City	3155 - 1329
1730 - 2210	Shale and lime	Conglomerate	3403 - 1577
2210 - 2510	Shale and shells	Arbuckle	3418 - 1592
2510 - 2985	Lime and shale	Rotary T.D.	3485 - 1659
2985 - 3030	Lime		
3030 - 3120	Lime and shale		
3120 - 3220	Lime		
3220 - 3422	Lime and shale		
3422 - 3460	Lime		
3460 - 3485	Lime and shale		
3485 -	T.D.		

200° 8 5/8" Surface Pipe Set

D.S.T. #1 3424 to 3438 - open 30 minutes weak blow, 4 minutes, recovered 7° of mud, no show of oil. I.S.I.P., 15 minutes zero pounds, F.S.I.P. 15 min. 420 pounds; flow pressures, zero pounds.

Dry and abandoned - plugged - 1-29-57 Plugging: Bottom plug 185° - Dumped 1/3 sack hulls - Dumped 20 sacks cement. Top plug @ 35°. Dumped 1/3 sack hulls. Dumped 10 sacks cement.

State of Kansas SS
County of Barton

B. E. Ash, owner of Bea Drilling Company, being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described were as filed and that the same are true and correct.

B. E. Ash
B. E. Ash

Subscribed and sworn before me this 12th day of Feb, 1957.

My commission expires April 27, 1957.

Virgil E. Belford, Jr.
Virgil E. Belford, Jr. - Notary Public

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE SEC	<u>5 T. 20 R. 12 W</u>
BOOK PAGE	<u>137 LINE 16</u>