

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER D & C 11-11-57

LEASE NAME Buckbee

WELL NUMBER I

SPOT LOCATION SE SW NW Sec.14

SEC. 14 TWP. 20 RGE. 12 (E) or (W)

COUNTY Barton

Date Well Completed 11-11-57

Plugging Commenced 02-13-84

Plugging Completed 02-20-84

MAR 20 1984

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Conservation Division  
Wichita, Kansas

ADDRESS P. O. Box 12116 Okla. City, OK 73157

PHONE (405) 949-7000 OPERATORS LICENSE NO. 5816

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? #6

Is ACO-1 filed? unknown If not, is well log attached? yes

Producing formation Arbuckle Depth to top 3375 bottom 3435 T.D. 3435

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3399	3403	8 5/8"	155	0
				4 1/2"	3435	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

See Back of this form

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kincaid Well Service License No. 1122, 1123, 727  
Address Box 276, Ellinwood, KS 67526

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Dorretta Moore (employee of operator) of  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) Dorretta Moore

(Address) Same as operator

SUBSCRIBED AND SWORN TO before me this 19th day of March, 1984

Patricia A. Wansley  
Notary Public

My Commission expires: 01-31-87

WORKMAN, N.W.  
Buckbee #1

TD 3435', PBTID 3404', 4½" csg @3435'. 2/13/84: MIRU PU, RIH w/tbg OE to 3255'. Circ 49 bbls 9 ppg mud to sfc. MIRU Howco. Spot 35 sk Cl A cmt f/3255-2800'. POH w/tbg. Pull 30,000 psi on csg, csg parted SDFN. 2-14: RIH w/tbg to 680'. Pmp 225 sk Cl A cmt w/2 sk Flocele. Closed BH, pmpd 125 sk Cl A cmt w/s sk flocele & 1 sk hulls. Cmt circ to sfc w/325 sk pmpd, WOC. Tagged TOC @220'. SDFN. 2-16: Atmpt to pmp dn csg, C/N. Pmpd 120 sk Cl A w/1½ sk hulls + 5 sk flocele dn-BH.

Topped off cmt. Cut csg off 5' below GL. Weld cap, ID well, restore loc & tank battery. Well P & A'd 2/20/84. State man Maricun Schmidt on loc.

## WELL LOG

ALPINE OIL &amp; ROYALTY CO., INC.

Commenced: November 2, 1957

Contractor: Quaker Drilling Co., Inc.

Completed: November 11, 1957

Alpine's Buckbee No. 1  
SE SW NW Sec. 14-20S-12W  
Barton County, Kansas

Elevation: 1814 KB

## Casing Record:

Set 8 5/8 inch casing at 165 feet with 200 sacks pozmix  
Set 4 1/2 inch casing at 3435 feet with 150 sacks pozmix

(Figures Indicate the Bottom of the Formations)


<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Sand	105	Anhydrite	595
Hard Sand	112	Heebner	2999 -1185
Streaks of Hard Sand and Shale	165	Brown Lime	3125 -1311
Shale and Red Bed	570	Lansing	3143 -1329
Shale	595	Base of Kansas City	3356 -1542
Anhydrite	620	Arbuckle	3375 -1561
Shale and Shells	1640	Rotary Total Depth	3435 -1621
Sandy Lime and Shale	1950		
Lime and Shale	2090		
Shale	2285		
Shale and Shells	2510		
Shale and Lime	3340		
Lime	3376		
Shale and Dolomite	3435		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SE SW NW of Section 14, Township 20 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: \_\_\_\_\_  
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me a Notary Public this 22nd day of November, 1957.

  
Virginia Mundeckl, Notary Public
MY COMMISSION EXPIRES:  
August 10, 1961RECEIVED  
STATE CORPORATION COMMISSION

DEC 8 1983

CONSERVATION DIVISION  
Wichita, Kansas