

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER D & C 03-09-59  
LEASE NAME Buckbee  
WELL NUMBER 5  
SPOT LOCATION NW NE SW Sec.14  
SEC.14 TWP.20 RGE.12 (W)  
COUNTY Barton  
Date Well Completed 03-09-59  
Plugging Commenced 02-14-84  
Plugging Completed 02-21-84

RECEIVED  
STATE CORPORATION COMMISSION  
TYPE OR PRINT  
Will out completely  
and return to Cons. Div.  
office within 30 days.  
MAR 20 1984

LEASE OPERATOR Gulf Oil Corporation  
ADDRESS P. O. Box 12116 Wichita, Kansas, OK 67215

PHONE (405) 949-7000 OPERATORS LICENSE NO. 5816

Character of Well Input  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? #6

Is ACO-1 filed? unknown if not, is well log attached? yes

Producing formation none Depth to top --- bottom --- T.D. 3375

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Injection	Open Hole		8 5/8"	200	-0-
				5 1/2"	3373	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

See back of this form

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kincaid Well Service License No. 1122,1123,727  
Address Box 276, Ellinwood, KS 67526

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Dorretta Moore (employee of operator) ~~is~~  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dorretta Moore  
(Address) Same as above

SUBSCRIBED AND SWORN TO before me this 19th day of March, 1984

Patricia A. W. Underly  
Notary Public

My Commission expires: 01-31-87

WORKMAN, N. W.  
Buckbee #5

TD 3375', PBTD 3375', 5½" csg @3373'. 2/14/84: MIRU Welex. RIH w/gauge ring to 3'. C/N get any further. MIRU PU w/mud pmp & pwr swl. RIH w/4-3/4" rock bit on 2-3/8" tbg. Cln hole to 3358'. POH w/tbg & tls. RIH w/2-3/8" tbg OE to 3350'. 3/16: MIRU Howco, estb circ to sfc. Spot 20 sk Cl A cmt w/1 sk hulls f/3350-3180'. Spot 9 ppg mud f/3170-2450'. Spot 100 sks Cl A cmt w/4 sk flocele f/2450-1600'. Spot 9 ppg mud f/1600-1400'. Spot 100 sk Cl A cmt w/4 sks flocele f/1400-465'. POH w/tbg. WOC, RIH w/2-3/8" tbg to TOC (465'). T/csg w/50 sk Cl A cmt. POH w/tbg. Tie onto BH. Pmp 130 sk Cl A cmt. Cut csg off 5' below GL. Cap well, ID well. Restore loc. Well P & A 2/20/84. State man Marion Schmidt on loc.