


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 14 Twp. 20S Rge. 12W (E) (W)  
Location as "NE/CNW&SW&S" or footage from lines: CNL SE NW  
Lease Owner ALPINE OIL & ROYALTY CO., INC.  
Lease Name LIZZIE BUCKBEE Well No. 2  
Office Address 1100 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 6, 1958 19  
Application for plugging filed March 6, 1958 19  
Application for plugging approved March 6, 1958 19  
Plugging commenced March 6, 1958 19  
Plugging completed March 6, 1958 19  
Reason for abandonment of well or producing formation non-productive in commercial quantities  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3408 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	178'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Circulated heavy mud - placed plug of hulls and wood at 150 feet with 20 sacks cement through drill pipe - Heavy mud to 35 feet - another plug of hulls and wood at 35 feet with 10 sacks cement on top

RECEIVED  
MAR 11 1958

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Quaker Drilling Co., Inc.  
Address 1100 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Dwight J. Wilson (employee, owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson  
1100 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of March 19 58

My commission expires August 10, 1961  
Eugene M. Murrell Notary Public.

PLUGGING  
TWP. 20S R. 12W  
BOOK PAGE 87 LINE 14

## WELL LOG

ALPINE OIL &amp; ROYALTY CO., INC.

Commenced: February 25, 1958

Contractor: Quaker Drilling Co., Inc.

Completed: March 5, 1958

Lizzie Buckbee No. 2  
CNL SE NW Sec. 14-20S-12W  
Barton County, Kansas

Elevation: 1807 KB

Production: D &amp; A

## Casing Record

Set 8 5/8 inch casing at 178 feet with 200 sacks pozmix

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Sand	105	Anhydrite	575 /1232
Hard Sand	110	Heebner	2984 -1177
Shale and Shells	178	Brown Lime	3109 -1302
Sand Streaks & Grey Shale	265	Lansing	3126 -1319
Red Bed	500	Base of Kansas City	3353 -1546
Shale	575	Conglomerate	3369 -1562
Anhydrite	605	Arbuckle	3387 -1580
Shale and Shells	1060	Rotary Total Depth	3408 -1601
Shale	1515		
Shale and Sandy Lime	1675		
Sandy Lime & Shale	2100		
Shale and Shells	2310		
Shale and Lime	2780		
Lime and Shale	2930		
Shale and Lime	3190		
Lime and Shale	3387		
Dolomite	3408		

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 11 1958  
CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the CNL SE NW of Section 14, Township 20 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: 

SUBSCRIBED AND SWORN to before me a Notary Public in and for Sedgwick County, Kansas this 6th day of March, 1958.

MY COMMISSION EXPIRES:  
August 10, 1961

  
Virginia Mundell, Notary Public

PLUGGING  
FILE SEC. 14 T. 20 R. 12W  
BOOK PAGE 87 LINE 14