

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Bartons County. Sec. 1 Twp. 20 Rge. (E) 12 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE SW WE

Lease Owner. J. G. Hensley

Lease Name. Wichita Farm Well No. B-5-

Office Address. Wichita Farm

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date, well completed. March 10 1944

Application for plugging filed. March 10 1944

Application for plugging approved. March 10 1944

Plugging Commenced. March 10 1944

Plugging Completed. March 10 1944

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. C. T. Alexander Great Bend Farm

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3390 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	250	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with 10.4 Mud from 3390 ft. to 250 ft.
put in Bridge and 40 sacks Cement with
Mud put in through 4 1/2 Drill pipe. Then
filled with mud up to 20 ft. of surface
put in Bridge and 5 sacks of Cement.
Cut off surface pipe at base of collar
Filled with dirt to surface level

3-21-1944

PLUGGING
FILE SEC 1-208 120
BOOK PAGE 110 LINE 45



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. G. Hensley Wichita Farm
Address 308 Robinson Olds, Wichita Kans.

STATE OF Kansas, COUNTY OF Sedgewick, ss.

Ralph Nelson (employee of owner) or (owner-operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Nelson

1011 E. Euclid McPherson Farm
(Address)


SUBSCRIBED AND SWORN to before me this 10 day of March, 1944

My commission expires September 10, 1947

Jan C. Johnson
Notary Public.

15.009.056.15.0000

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for J. H. Hershey Farm Wolf No. 1 Depth 3390'

Contractor Veeder Supply & Development Company Pipe 260' of 8-5/8" Surface casing

Location SE of NW Sec. 1 Twp. 20 Range 12

Commenced 2-23-44 Completed 3-10-44 County Barton State Kansas

Sand & gravel	0	120	120
Shale & shells	120	195	75
Iron	195	240	45
Shale & red bed	240	445	205
Red bed	445	595	150
Shale & shells	595	1435	840
Sandy lime & shale	1435	1590	155
Shale & lime	1590	1645	55
Sandy lime	1645	1775	130
Shale & lime	1775	1845	70
Sandy lime	1845	1920	75
Lime & shale	1920	2075	155
Shale & shells	2075	2225	50
Lime & shale	2125	2190	65
Shale & shells	2190	2330	140
Lime & shale	2330	2810	480
Lime	2810	2960	150
Lime & shale	2960	3160	200
Lime	3160	3390	230
Lansing Brown Lime	3068		
Lansing White Lime	3085		
Conglomerate	3341		
Arbuckle	3360		

AFFIDAVIT

STATE OF KANSAS)
MONTGOMERY COUNTY) SS:

EMMETT C. VEEDER, of lawful age, being duly and solemnly sworn on oath says:

I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state, that the above drilling log covering the Wolf #1 well in Section 1, Township 20, Range 12, Barton County, Kansas, is true and correct.

Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY.

By:

Emmett C. Veeder
President.

Subscribed and sworn to before me this 15th day of March, 1944.

Leo L. Loured
Notary Public

My commission expires: July 11, 1944

PLUGGING
FILE: SEC. 1 Twp. 20 Range 12
BOOK PAGE 110 LINE 45