

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas


WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Barton

County. Sec. 1 Twp. 20 Rge. (E) 12 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines Center N/2 NW/4 SW/4
Lease Owner Simpson Oil Company
Lease Name Schartz Well No. 1
Office Address 713 First Nat'l. Bldg., Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) Dry
Date, well completed 5-17 193. 40
Application for plugging filed 5-17 193. 40
Application for plugging approved 5-17 193. 40
Plugging Commenced 5-17 193. 40
Plugging Completed 5-17 193. 40
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 193.
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Alexander
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 3386 Feet.
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
					190'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was filled with heavy rotary mud through drill pipe from 3386' to 190', cement plug from 190' to 175', rotary mud from 175' to 12', cement plug from 12' to 6' bottom of cellar and surface casing flat capped

PLUGGING
FILE 3386-1-20 R 12W
BOOK 103 PAGE 37

RECEIVED
MAY 22 1940
STATE CORP. COMM.
CONSERV. DIV.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Simpson Oil Company
Address 713 First Nat'l. Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Sam Payne, Jr.

(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sam Payne, Jr.
713 First Nat'l. Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of May, 1940.

My commission expires March 30, 1944

SCHARTZ WELL NO. 1

Location: Center of N 1/2 NW 1/4 SW 1/4 of 1-208-12W, Barton County, Kansas
 Operator: Simpson Oil Company & Alpine Oil & Royalty Co., Inc.
 Contractor: Simpson & Noble, Inc. Elevation: 1794
 Commenced: 4-29-40 Potential: DRY
 Completed: 5-19-40

Log

Sand & gravel	135
Blue shale	150
Blue shale & shells	202
(13" csg @ 190)	
Blue shale	238
Red bed	410
Red bed and shells	550
Anhydrite	580
Shale	786
Shale and shells	1094
Salt, shale and shells	1220
Salt and shells	1340
Lime and shale breaks	1427
Lime and shale	1540
Broken lime	2038
Broken lime and shale	2138
Shale and lime shells	2295
Shale and shells	2490
Broken lime	2552
Broken lime and shale	2766
Lime	2815
Lime and shale breaks	2858
Broken lime	2910
Lime	2985
Shale and shells	3090
Lime (K. C.)	3238
Lime and shale breaks	3305
Broken lime and shale	3351
Lime	3386
Total Depth	3586

Handwritten notes:
 2085
 1794
 1291
 3114
 1794
 1550

Geological Tops

Topeka	2705
Lansing	3085
Arbuckle	3344
Spotted saturation	3346-82
Shaley dolomite	3344-73
Dolomite	3373-86

RECEIVED
 1 20 1940
 BOOK PAGE 103 LINE 37

