


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 1 Twp. 20S Rge. 12W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE SW SW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name MIKE SCHATZ NO. 2-B Well No. _____
Office Address 800 Bitting Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 10, 1960 19____
Application for plugging filed November 10, 1960 19____
Application for plugging approved November 10, 1960 19____
Plugging commenced November 10, 1960 19____
Plugging completed November 11, 1960 at 1:30 A. M. 19____
Reason for abandonment of well or producing formation non-productive in
commercial quantities
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3380 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	XXX 190'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from total depth to 180 feet - Bottom Plug at 180 feet
Wooden plug - 1/4th sack hulls and 25 sacks cement - top plug at
40 feet - wooden plug - 1/2 sack hulls and 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
12-29-60
DEC 29 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December, 19 60

My commission expires August 10, 1961
Notary Public.



R

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: November 3, 1960

Contractor: Quaker Drilling Co., Inc.

Completed: November 10, 1960

Mike Schartz No. 2-B
NE SW SW Sec. 1-20S-12W
Barton County, Kansas

Elevation: 1796 K. B.

Production: D. & A.

Casing Record:

Set 8 5/8 inch casing at 190 feet with 175 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Sand	100	Heebner	2961 -1165
Sand	130	Brown Lime	3085 -1289
Shale and Pyrite	190	Lansing	3102 -1306
Red Bed and Shale	500	Base of Kans. City	3333 -1537
Red Bed	568	Conglomerate	3338 -1542
Anhydrite	593	Arbuckle	3377 -1581
Shale and Shells	1330	Rotary Total	
Lime and Shale	1490	Depth	3380 -1584
Lime and Shale Streaks	1650		
Sandy Lime & Shale	1825		
Lime and Shale	1970		
Shale and Shells	2395		
Shale and Lime	2785		
Lime - Broken	2845		
Lime	2915		
Lime and Shale	2995		
Shale	3085		
Lime	3170		
Lime and Shale	3205		
Lime	3282		
Lime and Shale	3350		
Cherty Lime & Shale	3380		

RECEIVED
STATE CORPORATION COMMISSION

DEC 29 1960

CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NE SW SW of Section 1, Township 20 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: 

Dwight J. Wilson

SUBSCRIBED AND SWORN TO before me this 28th day of December, 1960.


Virginia Mandell, Notary PublicMY COMMISSION EXPIRES:
August 10, 1961