

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15.009.20518.0001

LEASE NAME Dewerff C-2

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER _____

SPOT LOCATION NW NE SW

SEC. 1 TWP. 20 RGE. 12W (E) OR (W)

COUNTY Barton

DATE WELL COMPLETED _____

PLUGGING COMMENCED 9-16-83

PLUGGING COMPLETED 9-28-83

LEASE OPERATOR Fell Oil & Gas Company

ADDRESS Box 466 Chase, Kansas 67524

PHONE # () _____ OPERATORS LICENSE NO. _____

CHARACTER OF WELL _____
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? YES

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Hays

IS ALC-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3386'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	202'	none
				5-1/2"	3384'	2525'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Plugged off bottom with 5 sacks cement and sanded to 3050'. Shot casing @2714', 2616', 2525' and pulled a total of 79 joints (2525') of 5-1/2" casing. Plugged well with 4 sacks hulls, 12 sacks gel, 65 sacks cement, 5 sacks gel, 1 sack hulls and 100 sacks cement. Plugging Complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050
ADDRESS Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, SS.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 29 DAY OF September, 19 83



Irene Hoover
NOTARY PUBLIC

MY COMMISSION EXPIRES: _____

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1983

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83