

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

BARTON County. Sec. 2 Twp. 20S Rge. (E) 12 (W)

Location as "NE/CNWSW" or footage from lines SE SW NW

Lease Owner JOHN S. MARTIN

Lease Name KNOP Well No. B 1

Office Address 323 N. MAIN HOISINGTON, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19____

Application for plugging filed _____ 19____

Application for plugging approved _____ 19____

Plugging commenced _____ 1971

Plugging completed 8-1 _____ 1971

Reason for abandonment of well or producing formation DRY

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DON TRUAN

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3360 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED BACK TO 3100'
DUMPED 5 SACKS CEMENT
DUMPED 16 SACKS MUD
PUMPED 100 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1971
CONSERVATION DIVISION
Wichita, Kansas


Name of Plugging Contractor LYNCH CASING PLUGGING CO
Address RT 4, GREAT BEND, KS

STATE OF _____, COUNTY OF _____, SS.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John S Martin
323 No. Main Hoisington, KS.
(Address)

Subscribed and sworn to before me this 25 day of August 1971



Notary Public.

COMPANY: Shelley-Miller Drilling Company
205 Miller Building
Wichita, Kansas

Rotary Drilling Commenced: April 2, 1962
Rotary Drilling Completed: April 10, 1962

LOCATION: Knop "B" No. 1
SE SW NW Sec. 2-208-12W
Barton County, Kansas

CONTRACTOR: Shelley-Miller Drilling Company
205 Miller Building
Wichita, Kansas

CASING RECORD: 8 5/8" - 20% new casing set @ 187', cemented with 150 sacks
Sunset cement.

4 1/2" National Tubing 9 3/4' seamless J 55 casing, set @ 3357'
3" off bottom, cemented with 100 sacks salt cement.

LOG
(Measurements from top of Rotary Bushing to bottom of formation)

140	Sand
190	Shale
235	Shale & Shells
375	Red Bed
600	Red Bed & Shale
620	Anhydrite
920	Red Bed & Shale
1420	Shale & Shells
1600	Shale & Lime
1925	Lime & Shale
2735	Shale & Lime
2835	Lime Topeka
3005	Lime
3095	Lime & Shale
3174	Lime
3190	Lime Kansas City
3360	Line Rotary T. D.

RECEIVED
STATE CORPORATION COMMISSION
AUG 3 1971
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, Richard A. Shelley, Partner of Shelley-Miller Drilling Company, hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHELLEY-MILLER DRILLING COMPANY

By Richard A. Shelley

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

BE IT REMEMBERED, that on this 16th day of April, 1962, before me, the undersigned, a Notary Public, duly commissioned in and for the county and state aforesaid, came Richard A. Shelley, Partner, and known to me to be the same person who executed the foregoing instrument of writing in behalf of Shelley-Miller Drilling Company, as a Partner of said company, and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My Commission Expires:
March 24, 1964

Leona M. Powers
Leona M. Powers - Notary Public