


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 2 Twp. 20S Rge. 12W (E) (W)
Location as "NE/CNW*SW*" or footage from lines SW NW SE
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name AHGRIM Well No. K 1
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed November 3, 1960 19
Application for plugging filed January 4, 1963 19
Application for plugging approved January 7, 1963 19
Plugging commenced January 8, 1963 19
Plugging completed January 10, 1963 19
Reason for abandonment of well or producing formation non-productive in
commercial quantities
If a producing well is abandoned, date of last production December 27 1962
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Arbuckle Depth to top 3355 Bottom _____ Total Depth of Well 3374 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	188	Cemented
				5 1/2"	3357	2862'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 3374 feet to 3340 feet, ran
5 sacks of cement from 3340 feet to 3320 feet,
Pumped 10 sacks of mud and 70 sacks of cement to plug
8 5/8" pipe

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1963

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Glenn and Smith Pipe Pulling Company
Address Box 114, Ellinwood, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of January, 19 63

My commission expires August 10, 1965

[Signature]
Notary Public

15.009.14479.0000

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: October 25, 1960

Contractor: Quaker Drilling Co., Inc.

Completed: November 3, 1960

Ahlgrim No. 1
SW NW SE Sec. 2-20S-12W
Barton County, Kansas

Elevation: 1802 K. B.

Casing Record

Set 8 5/8 inch casing at 188 feet with 175 sacks cement
Set 5 1/2 inch casing at 3357 feet with 100 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>
Sand and Gravel	138	Heebner 2970 -1168
Hard Sand	143	Brown Line 3092 -1290
Shale and Syrite	190	Lansing 3110 -1308
Shale and Shells	610	Base of Kansas
Anhydrite	605	City 3344 -1542
Shale and Shells	1450	Arbuckle 3355 -1553
Shale and Lime	1545	Rotary Total
Broken Lime	1570	Depth 3358 -1556
Sandy Lime and Shale	1690	
Lime and Shale	1870	
Sandy Lime	1885	
Shale and Shells	2355	
Shale and Lime	2495	
Shale and Shells	2635	
Lime and Shale	2770	
Lime with shale Streaks	2855	
Lime and Shale	3164	
Lime	3293	
Lime and Shale	3358	

RECEIVED
STATE CORPORATION
JAN 7 1963
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SW NW SE of Section 2, Township 20 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me a Notary Public this 20th day of December, 1960.

Virginia Mundell
Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1961