

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 2 TWP. 20S RGE. 12W E/W
Location as in quarters or footage from lines:
C NE/4, NE/4

Lease Owner Petro Energy Company of Kansas
Lease Name Hammer #1 Well No. 1
Office Address P. O. Box 1041, St. Joseph, Missouri 64501
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed July 26, 1982
Application for plugging filed July 26, 1982
Plugging commenced 8:00 PM, July 26, 1982
Plugging completed 9:45 PM, July 26, 1982
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ bottom T.D. 3400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud.
Plugged with 150 sacks down 8 5/8" casing;
10 sacks through 2" pipe in rathole. Used
50/50 Pozmix with 2% gel and 3% cc.
By Sun Cementing Company.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Ks. 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 82.



Agnes D. Wurst
Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- HAMMER #1

Located: C NE/4 NE/4, Section 2-20S-12W, Barton County, Kansas

OWNER: Petro Energy Company of Kansas

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 19, 1982

COMPLETED: July 26, 1982

TOTAL DEPTH: 3400'

LOGCASING RECORD

0 - 150 Sand
 150 - 587 Shale
 587 - 604 Anhydrite
 604 - 1600 Shale
 1600 - 3350 Lime and Shale
 3350 - 3354 Lime
 3354 - 3370 Lime and Shale
 3370 - 3379 Lime
 3379 - 3400 Arbuckle

Ran 5 joints 8 5/8", 20# OD casing.
 198.68' pipe set at 210' K.B. Cemented
 with 200 sacks 60/40 Pozmix with 3% cc.
 Plug down at 11:30 PM, 7-20-82, by Sun
 Cementing.

Plugged.

Deviation Surveys: 1° at 1600'
 3/4° at 2380'
 2° at 3354'

Sun Oilwell Cementing
A Division of BJ Hughes, Inc.

P. O. Box 169
GREAT BEND, KANSAS 67530

15.009.22846.0000

CEMENTING TICKET
and Invoice Number **No. 12594**

Date: <u>7/22/82</u>	Customer Order No.	Sec. <u>3</u>	Twp. <u>26</u>	Range <u>12</u>	Truck Called Out <u>S. C. 304</u>	On Location <u>7:30 PM</u>	Job Began <u>9:15 PM</u>	Job Completed <u>9:45 PM</u>
Owner <u>Beck & Co. of Kansas</u>	Contractor <u>CEMENTING WORK</u>				Charge To <u>Beck & Co. of Kansas</u>			
Mailing Address				City		State		

Well No. and Farm <u>Hanna #1</u>	Place <u>10 1/2 mi. W of Hanna</u>	County <u>Wagon Wheel</u>	State <u>KANSAS</u>
Depth of Well <u>3420</u>	Depth of Job	Casing {New} Size _____ Weight _____	Size of Hole Amt. and Kind of Cement <u>11 3/4" 1600 lb. Bulk</u>
Kind of Job <u>Pump in</u>	Drillpipe _____	Tubing _____	Cement Left in casing by {Rotary} {Cable} Truck No. <u>CT-22</u>

Condition of Well at time of Cementing Dry hole Type of Plugs _____

Pressure Circulating _____ Minimum _____ Maximum _____

Time Required Mixing Cement _____ min. Making Change _____ min. Pumping Cement _____ min.

Remarks Pump in 5 1/2" 50 lb. cement 3 1/2 hrs. 1 1/2" pipe in

Price/Reference No. _____
Price of Job <u>\$ 370.00</u>
Second Stage _____
Standby Truck _____
Other Charges _____
Pump Truck Mileage <u>15.00</u>

Cement <u>Beck & Co.</u>	Material Left on Location <u>100 lb. 5 1/2" pipe</u>
Helper <u>TERRY ROSSER</u>	District <u>WAGON WHEEL</u> State <u>KANSAS</u>

The above job was done under supervision of the owner, operator, or his agent whose signature appears below.

Prices Subject to Correction. _____ Agent of Contractor or Operator

SALES TICKET FOR MATERIALS

QUANTITY SACKS	BRAND AND TYPE	PRICE	TOTAL
<u>80</u>	<u>Common</u>		
<u>80</u>	<u>Pressure</u>		
<u>cc. 403</u>			
<u>AM. CI.</u>			
<u>Oil 20.00</u>			
Plugs:			
Delivered by Truck No. <u>21-25</u>	Handling and Dumping		
Delivered From <u>Beck & Co.</u>	Mileage <u>10</u>		
Signature of Operator <u>Karl Amundson</u>	Sales Tax		
	Total Charges		