


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway,  
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 7 Twp. 20S Rge. (E) 7W (W)

Location as "NE/CNW/SW" or footage from lines Cen. NW NE  
Lease Owner Lario Oil & Gas Company  
Lease Name Charles W. Monroe Well No. 1  
Office Address 301 S. Market, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 30, 1964  
Application for plugging filed (written) May 4, 1964  
Application for plugging approved (verbal) April 30, 1964  
Plugging commenced April 30, 1964  
Plugging completed April 30, 1964  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Holyrood, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3594 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	245.14	
					Set @ 238'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 230'. Pushed hull and plug bridge to 230'. 20 Sacks cement. Mud to 40'. Plug and hull bridge with 10 sacks of cement. 2 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 5 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.  
Address 514 Orpheum Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Leo Ross (employee of owner) or (State Representative) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo Ross  
301 S. Market, Wichita, Kansas, 67202 (Address)

SUBSCRIBED AND SWORN to before me this 4th day of May, 1964

My commission expires July 21, 1966 Notary Public.

LARIO OIL & GAS COMPANY  
 Chas. W. Monroe No. 1  
 Cen. NW/4 NE/4 Sec. 7-20S-7W  
 Rice County, Kansas

Drilling Commenced: April 22, 1964  
 Drilling Completed: April 30, 1964  
 Drilling Contractor: Gabbert-Jones, Inc.  
 Total Depth: Rotary 3597'  
 I.P. = D. & A.

CASING RECORD:  
 8 5/8" 245.14' Set @ 238'  
 Cem. w/ 225 sacks

<u>Formation</u>	<u>Depth</u>
Shale	239
Red bed & shale	270
Shale	1085
Lime & shale	1700
Shale & lime	2055
Shale & lime w/ sand	2200
Shale & lime	2350
Lime & shale	2505
Lime	2765
Lime & shale	2950
Lime	3372
Shale	3455
Shale & lime	3540
Shale & sand	3577
Lime	3597

<u>GEOLOGICAL TOPS:</u>	
Heebner	2762' (-1034)
Douglas	2790' (-1062)
Brown Lime	2901' (-1173)
Lansing	2940' (-1212)
Base Kansas City	3265' (-1537)
Chert Conglomerate	3314' (-1586)
Kinderhook	3345' (-1617)
Kinderhook Lime	3474' (-1746)
Misener Sand	3563' (-1835)
Maquoketa	3566' (-1838)
Viola	3592' (-1864)
Welex Log T.D.	3594' (-1866)
Rotary T.D.	3597' (-1869)

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 5 1964

CONSERVATION DIVISION  
 Wichita, Kansas