


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Rice County, Sec. 4 Typ. 20S Rge. 7 (E) (W) XX

Location as "NE/CNW/SW" or footage from lines C S/2-NE/4
Lease Owner Messman-Rinehart Oil Co.
Lease Name Engelland Well No. 2
Office Address 1432 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed May 29, 1974
Application for plugging filed May 29, 1974
Application for plugging approved May 29, 1974
Plugging commenced May 29, 1974
Plugging completed May 29, 1974
Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3320 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	226'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug @ 220' w/1/4 sx hulls & 25 sx cement
2nd Plug @ 40' w/1/4 sx hulls & 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1974
CONSERVATION DIVISION
Wichita, Kansas


Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Gloria Fawcett (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of June, 19 74

My commission expires _____



D Ann Drennan
Notary Public.

DRILLERS LOG

CASING RECORD:

8-5/8" @ 226'
w/140 sx cement

TOTAL DEPTH: 3320'

COMPANY:

Messman-Rinehart Oil Co.

CONTRACTOR:

Red Tiger Drilling Co.

COMMENCED:

May 21, 1974

COMPLETED:

May 29, 1974

DESCRIPTION:

C S/2 NE/4
4-20S-7W
Rice County,
Kansas

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	124	
Shale & Lime	124	135	
Shale	135	227	
Anhydrite	227	230	
Shale & Red Bed	230	1030	
Shale & Lime	1030	2385	
Shale, Lime & Sand	2385	2425	
Lime	2425	2540	
Lime & Shale	2540	2710	
Lime	2710	2722	
Shale	2722	2726	
Shale, Lime & Sand	2726	2835	
Shale & Lime	2835	2865	
Lime	2865	2931	
Lime & Shale	2931	3002	
Lime	3002	3320	

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1974
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 6th day of June, 1974.

D. Ann Drennan
Notary Public

My Commission Expires:
December 28, 1977

