

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-159-20598.0000

LEASE NAME Keller

WELL NUMBER #1

2970 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 4 TWP. 20 RGE. 7 (E) or (W)

COUNTY Rice

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-25-91

Plugging Completed 3-28-91

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS Box 8647, Wichita, Ks. 67208

PHONE# 816-672-6373 OPERATORS LICENSE NO. 8061

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 25, 1991 (date)

by Glen Ward (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				5-5/8"	257'	None
				5-1/2"	3375'	2,328.01'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Dumped sand to 3200' and 5 sacks cement. Shot casing at 2547' and 2314'. Pulled 74 joints of 5-1/2" casing. B.J. Services plugged well with 35 sacks at 1075', 35 sacks at 675' and 100 sacks 60/40 pozmix cement with 2% gel, circulated to surface from 307'.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc. of Kansas

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
James W. Rockhold  
(Address) Box 698, Gt. Bend, Kansas 67530

RECEIVED  
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 29th day of March, 1991

APR 01 1991

CONSERVATION DIVISION  
Wichita, Kansas My Commission Expires:

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-91

Notary Public