


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines C NW $\frac{1}{4}$ NW $\frac{1}{4}$ SE $\frac{1}{4}$
Lease Owner Schermerhorn Oil Corporation
Lease Name Bradley Well No. 1
Office Address First National Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 2-21 19 53
Application for plugging filed 2-21 19 53
Application for plugging approved 2-21 19 53
Plugging commenced 2-21 19 53
Plugging completed 2-28 19 53
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3690 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	795	8-5/8		Left in

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3690 to 850 Mud
850 to 790 Cement
790 to 300 Mud
300 to bottom cellar cement

3-7-53

RECEIVED
STATE CORPORATION COMMISSION

MAR - 7 - 1953

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Badger Drilling Company
Address Great Bend, Kansas

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
Ola Williams (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

This is a certified true copy.

(Signature) (Signed) Ola WilliamsAlbert, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 6th day of March, 19 53My commission expires January 7, 1956

23-8390-s

6-51-20M

PLUGGING

FILE SEC 17-20-1426
BOOK PAGE 82 LINE 11

Kans. Corp. Comm.

15.009.00110.0000

BRIDLEY NO. 1

NE 1/4 Sec 32 Section 11-20E-14N
Barton County, Kansas
SCHNEIDERMAN OIL CORPORATION

8 5/8" O. D. Casing cemented at 795'
Drilling started 2-10-53
Drilling completed - Hole plugged 2-23-53

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>REMARKS</u>
0'	150'	Sand and clay	
150'	270'	Shale	
270'	335'	Sand	
335'	555'	Sand red bed	
555'	640'	Shale and sand	
640'	794'	Shale	
794'	800'	Anhydrite	8 5/8" O. D. Casing
800'	820'	Anhydrite	Cemented at 795'
820'	1550'	Shale shells	
1550'	1635'	Shale lime	
1635'	2940'	Shale and lime	
2940'	3500'	Lime	
3500'	3540'	Conglomerate	
3540'	3575'	Lime	Hole plugged

This is a true copy of the Driller's log as shown on the
Drilling Reports.

RANGER DRILLERS, INC.

By: W. A. Sherman

Subscribed and sworn to before me on this 3rd day of March, 1953.

My commission expires: June 7, 1956

Eva M. Davis
Notary Public

PLUGGING	
FILE	SEC <u>11</u> T <u>20E</u> R <u>14N</u>
BOOK	PAGE <u>82</u> LINE <u>11</u>

CONSERVATION DIVISION
Wichita, Kansas