

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock,
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 009 - 20629.0000 (of this well)

Operator's Full Name Lindsay Pipe & Supply

Complete Address Box 487 Chase, Kansas 67524

Lease Name Buckbee Well No. 1

Location SE SE SW Sec. 14 Twp. 20 Rge. 12 (W) X

County Barren Total Depth 3370'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelse Casing Pulling

Address Box 176 Chase Kansas 67524 License No. 683

Operation Completed: Hour 10:30 AM Day 22 Month 12 Year 1978

The above well was plugged as follows:

- Sanded back to 3315 and 5 sx cement with dump bailer.
- Squeezed thru 8 5/8" surface casing with 3 sx hulls.
- 30' sx mud gel ~~1~~ 1 sx hulls, and 100 sx cement.
- Max pres. 700#. Shut in pres. 500#.
- Recovered 2301' of 5 1/2" casing.
- 3365' of 5 1/2" casing cemented with 75 sx cement.
- 235' of 8 5/8" surface casing cement circ.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED 26 DEC 1978 12-26-1978

Signed: Dennis L Rankin
Well Plugging Supervisor

DATE 12-28-78 CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 8815-4