

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Kewanee Oil Company

Complete Address P. O. Box 2093, Wichita, Kansas 67201

Lease Name Buckbee Well No. # 3

Location SW SE NW Sec. 14 Twp. 20 Rge. 12 (E) (W) W

County Barton Total Depth 3375

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company

Address Box 364, Great Bend, Kansas License No. # 399

Operation Completed: Hour 10:00 A.M. Day 22 Month 2 Year 1973

The above well was plugged as follows:

8 5/8" csg. 180' Cwc.

Sanded hole back to 3350' & dumped 5 sax cement with dump bailer. Pulled pipe.

Squeezed well with 3 sax hulls, 20 sax mud, plug, & 100 sax cement with Halliburton

Cementing Company's pump truck, cementing from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Don Truman*
Well Plugging Supervisor

DATE 2/28/73

INV. NO. 9028-W