

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 31 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Shelly Miller
Complete Address: 505 Miller Bld - Wichita Kansas
Lease Name Kross Well No. 2
Location Se - 24th Sw Sec. 2 Twp. 20 Rge. 12 (E) (W)
County Barton Total Depth 3375
Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co
Address: Great Bend, Kansas License No. 2

Operation Completed: Hour 8pm Day 24 Month July Year 1962

The Above well was plugged as follows:

P.D. 3375' - 4 1/2" set at 3367 - 8 5/8" - 189'
Sand to 3350' and dumped 4 sac cement with dump
pair. Shot pipe at 2800' and pulled same out of hole.
Chunk mud to 180' built rock bridge and displaced
20 sac cement, chunk mud to 40' built 10" solid
rock bridge and 10 sac cement

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/1/62
INV. NO. 5466-W

Signed: Robert P. Leiker
Well Plugging Supervisor