

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 29 1967  
3-29-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Charles Hulme Drilling Contractor

Complete Address: Box 836, Great Bend, Kansas

Lease Name Tammen Well No. # 4

Location NE NE NE Sec. 31 Twp. 20 Rge. 12 (E) (W) W

County Barton Total Depth 3490

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. # 49

Operation Completed: Hour 1 PM Day 23 Month 3 Year 1967

The Above well was plugged as follows:

8 5/8" 271' Cwc.

Sanded hole back to 3460' & dumped 5 sax cement with dump bailer. Pulled pipe.

Mudded hole to 265', set 15' rock bridge, & displaced 10 sax cement. Let set

over night, bailed hole dry, & displaced 4 yds. ready-mix cement, cementing from

250' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Truman  
Well Plugging Supervisor

DATE 3/29/67

INV. NO. 4992-W