

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE NE NWSEC. 30 TWP. 20 RGE. 18-WDry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease WelshOperator Steeling Drilling Co. Address Steeling-Kans.Field _____ County BartonTotal Depth 3489 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 180 ft. Pigeonated with cement.
5 1/2" casing at 3470 ft. Cemented with 50 sacks cement.
Plugged back to 3460 ft. with chert. Dumped 5 sacks
of cement at 3460 ft. Shot off & pulled the 5 1/2" casing
and to 180 ft. Set Rock Bridge & 14 sacks
of cement at 180 ft. Mud to 30 ft. Plug
x 10 sacks of cement at the surface.

RECEIVED

STATE CORPORATION COMMISSION

PLUGGING

JAN 31 1951

FILE SEC. 30 TWP. 20 RGE. 18-W
CONSERVATION DIVISION
BOOK PAGE 59 LINE 3 Kansas

C. W. Stangl -
District Conservation AgentDate 1-27-51