

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts
Administrator
500 Insurance Building
Wichita 2, KansasOperator's Full Name Apex Supply CompanyComplete Address: West 10 Street, Great Bend, KansasLease Name Krone Well No. 1Location NE SE SW Sec. 30 Twp. 20S Rge. 12 (E) / (W)County Barton Total Depth 3555Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling CompanyAddress: Chase, Kansas Box 304 License No. 436Operation Completed: Hour Day 16 Month July Year 1959

The Above well was plugged as follows:

225 feet of 8 5/8 inch surface casing circulated with cement.;Total depth 3555 feet. Checked the hole to 3532 feet and foundit open. Filled with sand to 3490¹/₂ feet and dumped 5 sacks ofcement with bailer. Pulled 2909 feet of 5¹/₂ inch casing. Clearedhole and bailed hole to 225 feet; set 10 rock bridge and dumped20 sacks of cement. Mudded the hole to 40 feet; set 10 foot rockbridge and ran 10 sacks of cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSIONSigned: Don L. Driscoll

Well Plugging Supervisor

MAR 16 1967

CONSERVATION DIVISION
Wichita, Kansas

15.009.07396.0000

Dear Don:

We have misfiled the agents report for the plugging of the Krone Well #1. You plugged this well back in July, 1959. We have completed another report for your signature and if you will sign and return this to us, we will promise not to lose this one.

S. S. Greider.