

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

BARTON County. Sec. 35 Twp. 20 Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines. C S/2 NW NE

Lease Owner J.L. CHEW

Lease Name WEATHERS Well No. 1

Office Address BOX 526, LYONS, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL

Date well completed JUNE 28 1947

Application for plugging filed JULY 17, 1965

Application for plugging approved 19

Plugging commenced 7/17/65 19

Plugging completed 7/24/65 19

Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DON TRUAN

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3543 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	813'	NONE
				5 1/2"	3537'	1867'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3537' - 3270' - PLUG  
 3270' - 3240' - SAND  
 3240' - 3200' - FIVE SACKS CEMENT  
 3200' - 350' - MUD  
 350' - 340' - ROCK BRIDGE  
 340' - 325' - FIVE SACKS CEMENT  
 325' - BASE - FIVE YARDS READY-MIX

RECEIVED  
STATE CORPORATION COMMISSION

8-16-65  
AUG 16 1965

Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC (If additional description is necessary, use BACK of this sheet) **CONSERVATION DIVISION**  
Address BOX 562, GREAT BEND, KANSAS **Wichita, Kansas**

STATE OF KANSAS COUNTY OF BARTON, ss.  
J.L. NUTT (Employer/Owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
BOX 562, GREAT BEND, KANSAS

(Address)

SUBSCRIBED AND SWORN to before me this 3RD day of AUGUST, 1965

My commission expires Jan. 26, 1967

Carmen R. Cook  
Carmen R. Cook, Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


15.009.19469.0000

Company C. W. TRICKETT, ET AL  
Farm - Leathers No. 1

SEC. 35 T. 20 S. 11N  
CS $\frac{1}{2}$  NW NE

Total Depth. 3543'  
Comm. 6-14-47 Comp. 6-28-47  
Shot or Treated.  
Contractor. Sterling Drlg. Co.  
Issued. 7-24-48

County. Barton  
KANSAS



Elevation. \_\_\_\_\_

Production. Minimum Well

Figures indicate Bottom of Formations.

sand	190
shale & li e	375
red bed & sand	510
red bed	685
shale	803
anhydrite	825
shale & red bed	1250
shale & salt	1710
lime	2295
lime brkn	2385
shale & shells	2650
shale & lime	2855
lime	3215
shale & lime	3250
shale & shells	3280
lime	3510
lime & shale	3536
Arbuckle lime	3543
Total Depth	

RECEIVED  
STATE CORPORATION COMMISSION

AUG 16 1935

CONSERVATION DIVISION  
Wichita, Kansas