


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavits
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rice County. Sec. 34 Twp. 20S Rge. 9W (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines NE NW NE
Lease Owner Sterling Drilling Company, et al
Lease Name Hartle Well No. 1
Office Address Box 127, Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 27 19 63
Application for plugging filed November 27 19 63
Application for plugging approved November 27 19 63
Plugging commenced November 27 19 63
Plugging completed November 27, 2:45 p. m. 19 63
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3415 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	202.67'	none.
					set at	
					210.67'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 200'. Plug at 200', 1/4 sack hulls on plug. 25 sacks cement.
Heavy mud up to 40'. Plug at 40', 1/4 sack hulls on plug. 10 sacks cement to base of cellar. Bridge in rat hole, 2 sacks cement below plow depth.

Plugging complete at 2:45 p.m.

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1963 12-2-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Group Exploration Company
Address Box 127, Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
William Shepherd (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William Shepherd
William Shepherd, Geologist
Sterling, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of November, 19 63

My Commission Expires Jan. 22, 1966
BERNARD LAUDERMILK

Bernard Laudermilk
Bernard Laudermilk Notary Public.

My commission expires _____

15.159.30445.0000

GROUP EXPLORATION COMPANY
Sterling, Kansas

WELL LOG ----- Hartle #1
Located: NE NW NE Section 34-20S-9W, Rice County, Kansas.

OWNER: Sterling Drilling Company, Etal
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 11-20-63
COMPLETED: 11-26-63

ROTARY TOTAL DEPTH: 3415'

LOG

CASING RECORD

0	-	140	Sand & Shale
140	-	1120	Shale & Shells
1120	-	1455	Lime & Shale
1455	-	1850	Lime
1850	-	2210	Lime & Shale
2210	-	2390	Lime
2390	-	2653	Lime & Shale
2653	-	2785	Lime
2785	-	2995	Shale & Lime
2995	-	3360	Lime
3360	-	3397	Lime & Sand
3397	-	3415	Lime T.D.

Set 8-5/8" Surface Casing @ 210.67' K.B.
with 210 sacks Pozmix #1 with HA-5.

Plugged and Abandoned.

RECEIVED
STATE CORPORATION COMMISSION

DEC 6 1963

CONSERVATION DIVISION
Wichita, Kansas