


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 34 Twp. 20S Rge. 9 (W)

Location as "NE/CNW/SW" or footage from lines NW SE NE
Lease Owner Jay-Bee Oil Company, Inc.
Lease Name Hartle Well No. 1
Office Address 515 Union Center Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 29 1968
Application for plugging filed Verbal Approval 19
Application for plugging approved Verbal Approval 19
Plugging commenced April 29 1968
Plugging completed April 29 1968
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	208	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3430 feet (rotary total depth) to 200 feet. Set bottom plug at 200 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented to cellar with 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, INC.
Address 200 N. Main St., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 N. Main St., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of May, 1968

My commission expires April 21, 1971
Martha Hartpence
Martha Hartpence Notary Public.

15.159.20117.0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Jay-Bee Oil Company, Inc.

SEC. 34 T. 20S R. 9W

FARM Hartle No. 1

LOC. NW SE NE


TOTAL DEPTH 3,429'
 COMM. April 20, 1968
 SHOT OR TREATED
 CONTRACTOR H-30, INC.
 ISSUED

COMP. April 29, 1968

COUNTY Rice

KANSAS

RECEIVED
 STATE CORPORATION COMMISSION
MAY 3 1968
 CONSERVATION DIVISION
 Wichita, Kansas



CASINO

20 10
 15 8-5/8" 208' cemented w/185 sx cement ELEVATION 1,691 KB
 12 6
 13 5

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

ELECTRIC LOG TOPS

Surface Soil & Sand	70		
Red Shale & Sand Streaks	160	Heebner	2764 -1073
Shale	248	Brown Lime	2901 -1210
Anhydrite	263	Lansing	2938 -1247
Shale	695	Base K.C.	3228 -1537
Shale & Salt	1061	Maquoketa	3274 -1583
Shale & Lime	1270	Viola	3306 -1615
Lime & Shale	1300	Simpson Shale	3351 -1660
Shale w/Lime Streaks	1473	Simpson Sand	3362 -1671
Lime & Shale	2059	Base Simpson Sand	3367 -1676
Shale w/Lime Streaks	2340	Arbuckle	3413 -1722
Shale & Lime	2720	Log T.D.	3429 -1738
Lime w/Shale Streaks	2845	Rotary T.D.	3430 -1739
Lime	3430		
Rotary Total Depth	3430		

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer

 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 2nd day of May, 1968.

Martha Hartpence

 Martha Hartpence - Notary Public

My Commission Expires:

April 21, 1971