


STATE OF KANSAS
STATE CORPORATION COMMISSION

R

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 31 Twp. 20 Rge. 9 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE/4 NE/4 NE/4
Lease Owner Richard E. Smith
Lease Name CAYWOOD Well No. 2
Office Address Box 550, Hutchinson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 20, 1972 19 72
Application for plugging filed " 19 72
Application for plugging approved " 19 72
Plugging commenced June 20, 1972 19 72
Plugging completed June 20, 1972 19 72
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Herman Justus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3340 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1972
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full of heavy mud to 500' - Set Plug & 25 sacks cement thru drill pipe.
Come up hole to 190' - ^{Set} Plug with 25 sacks cement
Set top plug at 40' w/1/2 sacks hulls & 10 sacks cement.
~~2~~ sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas, COUNTY OF Barton, ss.
Leonard Williamson (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson

Box 823-Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20 day of June, 1972.

My commission expires 4-11-1974

Nancy M. Hays
Notary Public.

W E L L L O G

DATE COMMENCED: June 13, 1972
DATE COMPLETED: June 20, 1972

Richard E. Smith
CAYWOOD #2
SE/4 NE/4 NE/4
Sec. 31-T20-R9w
Rice County, Kansas

ELEVATION: 1709 K.B.

0	-	90'	Sand
90	-	310'	Red Bed
310	-	330'	Anhydrite
330	-	590'	Red Bed
590	-	1185'	Shale & Shells
1185	-	1700'	Shale & Lime Streaks
1700	-	1785'	Lime-Shale streaks
1785	-	2508'	Shale - Lime
2508	-	2795'	Lime
2795	-	2799'	Shale
2799	-	2820'	Shale - Lime
2820	-	2827'	Lime
2827	-	2924'	Shale
2924	-	2955'	Lime - Shale
2955	-	3241'	Lime
3241	-	3246'	Lime - Shale
3246	-	3272'	Conglomerate
3272	-	3279'	Congl - Sand
3279	-	3282'	Shale -Simp.
3282	-	3328'	Sand - Shale -
3328	-	3340'	Dolomite
		3340'	RTD

FORMATION DATA

ANHYDRITE	310'
TOPEKA	2508'
HEEBNER	2795'
TORONTO	2820'
DOUGLAS	2827'
BR. LIME	2924'
KANSAS CITY	2955'
BASE K.C.	3241'
CONGLOMERATE	3246'
CONGLOMERATE SD	3272'
SIMPSON SHALE	3279'
SIMPSON SAND	3282'
ARBUCKLE	3328'
RTD	3340'

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1972
CONSERVATION DIVISION
Wichita, Kansas

SURFACE CASING: Set used
8-5/8" 28# surface pipe at
198' with 200 sacks cement,
2% Gel, 3% Ca.Ch.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Leonard Williamson of lawful age, does swear and state that
the facts and statements herein contained are true and correct to the
best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 20 day of June 1972

My Comm. Expires:

April 11, 1974

Deborah M. Maguire
Notary Public