

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Malone Oil Company

ADDRESS 1591 Rugby Circle Thousand Oaks, CA 91360

PHONE (805) 497-9801 OPERATORS LICENSE NO. 7546

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3340'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	200'	none
				5 1/2	3337'	2413'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s.
Sanded bottom to 3196' & ran 5 sks cement. Shot csg at 2413', came loose. Pulled csg to 1150', pumped 35 sks cem w/100# hulls. Pulled to 750', pumped 35 sks cement w/100# hulls. Pulled to 250', pumped 70 sks cement & circulated to surface. Pulled rest of casing & topped with 25 sks. Plugging complete. 60/40 poz 4% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Malone Oil Company

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 5th day of May, 19 97

Irene Herzberg
 Notary Public

My Commission Expires:

