


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 30 Twp. 20s Rge. 9 West (E9) (W)

Location as "NE/CNWxSWx" or footage from lines SW/4 NE/4 SE/4
Lense Owner Icer Addis
Lease Name JOHN CAYWOOD Well No. 2
Office Address 312 Petroleum Building, Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 31, 1972
Application for plugging filed August 31 1972
Application for plugging approved August 31 1972
Plugging commenced August 31 1972
Plugging completed August 31 1972
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Gilbert Toman

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud to 500'
Set Plug and 40 sacks cement thru drill pipe
Come up hole to 200' - Set Plug and 25 sacks cement
Top plug set at 40' with 1/2 sk. hulls and 10 sacks cement.
2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 1972

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF Kansas, COUNTY OF Barton, ss.
Leonard Williamson (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
Box 823- Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 31 day of August 1972.

Notary Public

My commission expires April 11, 1974

DRILLERS' WELL LOG

DATE COMMENCED: August 24, 1972
DATE COMPLETED: August 31, 1972

Icer Addis
JOHN CAYWOOD #2
SW/4 NE/4 SE/4
Section 30-Twp.20S,Range 9 W
Rice County, Kansas

0	-	135'	Sand - Shale
135	-	334'	Red Bed
334	-	353'	Anhydrite
353	-	650'	Red Bed
650	-	1180'	Shale
1180	-	1365'	Shale & Lime Streaks
1365	-	1670'	Shale & Lime
1670	-	1880'	Lime & Shale Streaks
1880	-	2595'	Shale - Lime Streaks
2595	-	2798'	Lime & Shale Streaks
2798	-	2803'	Shale
2803	-	2822'	Shale & Lime
2822	-	2831'	Lime
2831	-	2925'	Shale
2925	-	2956'	Br. Lime
2956	-	3245'	Lime
3245	-	3250'	Shale
3250	-	3300'	Conglomerate
		3300'	RTD

ELEVATION: 1716 K.B.

FORMATION DATA

ANHYDRITE	334
HEEBNER	2798
TORONTO	2822
DOUGLAS	2831
BR. LIME	2925
KANSAS CITY	2956
BASE K.C.	3245
CONGLOMERATE	3250
R.T.D.	3300

SURFACE PIPE: Set new
8-5/8" surface pipe, 20#
at 206' with 175 sacks
60-40 pozmix, 2% Gel, 3% Ca.
Ch.

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 1972

CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age does swear and state that
the facts and statements herein contained are true and correct to the
best of his knowledge.

Leonard Williamson
Leonard Williamson

Subscribed and sworn to before me this 31 day of August 1972.

Kathryn M. Hague
Notary Public

My Comm. Expires:
April 11, 1974.