

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

		X	

Locate well correctly on above
Section Plat

Barton County, Sec. 31 Twp. 20 Rge. 12 (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines SE - NW - NE
Lease Owner Charles Hulme Drilling Cont.
Lease Name Tammen Well No. 3
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 4-26 1956
Application for plugging filed 6-29 1957
Application for plugging approved 6-29 1957
Plugging commenced 7-6 1957
Plugging completed 7-9 1957
Reason for abandonment of well or producing formation CEASED TO PRODUCE
If a producing well is abandoned, date of last production MAY 6 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation ARBUCKLE Depth to top _____ Bottom _____ Total Depth of Well 3475 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	222	None
				5 1/2	3463	2878.15

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 3465 to 3450 - dumped 5 sks cement - pulled casing - mudded hole to 215' - set rock bridge - dumped 1 sk Calseal - bailed fluid - could not bail off - dumped 8 sks cement on plug - bailed fluid off plug - dumped 12 sks cement - mudded to 20' - set rock bridge - dumped 5 sks cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 569 Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
C. E. Ryars (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Ryars
P.O. Box 36, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15 day of July 1957
My commission expires October 15, 1957
Ray Richardson Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1957
7-17-57
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 31 T. 20 R. 12W
BOOK PAGE 24 LINE 24

WELL LOG

Company - Chas. Hulme Drilling Contractor

SE - NW - NE
 Sec. 31-20S-12W
 Barton County, Kansas

Farm - Tammen Well No. 3

Total Depth - 3465'

Comm. - April 11, 1956 Comp. - April 29, 1956 Elevation - 1857' RB

Contractor - Chas. Hulme Drilling Contractor

Casing - 8 5/8" @ 222' w/300 sacks cement and 2% calcium chloride
 5 1/2" @3463' W/75 Sacks and 1 sack Calcium Chloride

0	170	Sand	
179	222	Blue Shale & Shells	
222	665	Red Bed & Shale	<u>Tops</u>
665	690	Anhydrite	
690	1275	Shale & Shells	Anhydrite 665'
1275	1380	Salt & shale	Heebner 3078'
1380	1995	Lime	Brown Lime 3202'
1995	2195	Lime & Shale	Lansing 3217'
2195	2570	Shale & Shells	Conglomerate 3441'
2570	2835	Shale & Lime	Arbuckle 3461'
2835	2955	Lime	
2955	3055	Lime & Shale	
3055	3465	Lime	
3465		T.D.	

State of Kansas)
 County of Barton) ss:

I, C. E. Byars, of Chas. Hulme Drilling Company upon oath state that the above and foregoing is a true and correct copy of the log of the Tammen # 3 well.

 C. E. Byars

Subscribed and sworn to before me this 2nd day of May, 1956

 Notary Public

My Commission Expires: October 15, 1957

RECEIVED
 STATE CORPORATION COMMISSION

JUN 29 1957

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 31 T 20 R 12W
 BOOK PAGE 24 LINE 24