


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Barton County, Sec. 31 Twp. 20 Rge. 12 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NE NW

Lease Owner Morris Sitrin, Inc.

Lease Name Spacil M/1 Well No. \_\_\_\_\_

Office Address Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_\_\_

Plugging commenced 4/15/70 \_\_\_\_\_ 19\_\_\_\_

Plugging completed 4/21/70 \_\_\_\_\_ 19\_\_\_\_

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truan

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3558 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	240	none
				5 1/2"	3558	2827'

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 3250', ran rocks, sand and 5 sacks of cement.  
S hot pipe at 2894', loaded hole with 70 barrels water.  
Pulled pipe into in cellar, shot pipe at 2796', pulled 86  
joints. Squeezed well with 20 sacks gel mud and 90 sacks  
of cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight

CHASE, KANSAS

(Address) \_\_\_\_\_ 19 70

SUBSCRIBED AND SWORN to before me this 24th day of April, 19 70



Margaret Malcher  
Notary Public.

My commission expires 2/15/71

SPACIL # 1 - NE NW/4 Section 31-20-12<sup>th</sup> Barton County, Kansas  
 Company - Virginia Drilling Co Inc.  
 Contractor - same  
 Commenced - May 16, 1956  
 Completed - May 28, 1956  
 C. Tools - 6/11/56  
 Total Depth - 3560  
 Elevation - 1850 Gr.

8 5/8" casing set at 240 ft.  
 3 1/2" casing set at 3550 ft.

FORMATION	DEPTH
Sand-surface clay-gravel	0- 175
Shale-shells	175- 240
Red bed -shale	240- 280
Red bed -sand	280- 669
Anhydrite	669- 693
Shale-shells	693-1525
Lime-shale	1525- 1635
Lime	1635-1705
Lime-shale	1705-2010
Shale-shells	2010-2140
Lime	2140-2185
Lime-shale	2185-2299
Shale-shells	2295-2575
Lime-shale	2575-2743
Lime	2743-3065
Lime-shale	3065-3160
Shale?	3160-3250
Lime	3250-3440
Conglomerate	3440-3475
Artucklelime	3475-3560. % D

TOPS:

- 3080 - Keokuc
- 3202 - Bra line
- 3217 - Kansas City
- 3457 - Artuckle

*[Signature]*  
 F. A. Murphy

Subscribed and sworn to before me, a Notary Public,  
 this 28<sup>th</sup> day of June, 1956.

*[Signature]*  
 Notary Public

My commission expires: 2-5-57

*28/57 - 3474 - 3479 - 20 shots*

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 24 1970  
 CONSERVATION DIVISION  
 Topeka, Kansas