


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Flat

Barton

County. Sec. 30 Twp. 20S Rge. 12 E (W)

Location as "NE/CNW/4SW/4" or footage from lines NE/4 NE/4 NW/4

Lease Owner Messrs. J. A. Davis and J. H. Child, et al

Lease Name Welsh Well No. 1

Office Address 121 West Second, Hutchinson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed October 4 19 50

Application for plugging filed January 22 19 51

Application for plugging approved January 22 19 51

Plugging commenced January 26 19 51

Plugging completed January 27 19 51

Reason for abandonment of well or producing formation Unprofitable production

If a producing well is abandoned, date of last production January 14 19 51

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough

Producing formation Arbuckle Depth to top 3465' Bottom 3489' Total Depth of Well 3489' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	280'	
				5 1/2"	3470'	2548'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to

feet for each plug set.

1-26-51: Mudded to 280'. Dumped 4 sacks cement with bailer.

1-27-51: Dumped 11 more sacks at 280'. Filled with heavy mud to 30'. 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1951
CONSERVATION DIVISION
Wichita, Kansas

2-3-57

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sterling Drilling Company
Address Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.

Rollin Mead

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Rollin Mead

Sterling, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 1st day of February, 1951


My Commission Expires Sept. 17, 1953

My commission expires

Notary Public.

28-5091-S

8-50-10M



STERLING DRILLING COMPANY

STERLING, KANSAS

WELL LOG ----- WELSH #1

Location - NE/4 NE/4 NW/4 of Section 30-20S-12W, Barton County, Kansas.

Owner - Messrs. J. A. Davis and J. H. Child, Et Al
Contractor - Sterling Drilling Company

Commenced - 9-11-50.

Completed - 9-24-50 (w/r)
- 10-4-50 (w/c.t.)Total Depth - 3474' (w/r)
- 3489' (w/c.t.) -ELEVATION: 1850 DF
1848 GrLOG

0-- 280	Sand and Clay
280-- 925	Red Bed, Sand, Shale, Shells
925-1350	Shale and Red Bed
1350-1510	Shale
1510-2020	Lime
2020-2130	Lime and Shale
2130-2140	Shale and Shells
2140-2205	Shale and Lime
2205-2495	Shale and Shells
2495-2815	Shale and Lime
2815-2870	Topeka Lime
2870-2940	Lime
2940-3030	Lime and Shale
3030-3080	Lime
3080-3195	Lime and Shale
3195-3208	Brown Lime
3208-3243	Kansas City Lime
3243-3425	Lime
3425-3446	Lime and Shale
3446-3465	Conglomerate
3465-3474	Arbuckle Lime
3474-3485	Lime and Shale
3485-3489	Lime

CASING RECORD280' of 8-5/8" Surface Pipe
Cemented with 175 Sacks Cement3470' of 5 1/2" Casing
Cemented with 50 Sacks CementFORMATION TOPS

Heebner	3067'
Brown Lime	3189'
Lansing	3206'
Conglomerate	3440'
Arbuckle	3465'

PRODUCTION PRODUCER
RECEIVED
 STATE CORPORATION COMMISSION

FEB 3 1951
 CONSERVATION DIVISION
 Wichita, Kansas

