

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

3-5

15-009.04923.0000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER _____
LEASE NAME Phillips
WELL NUMBER #3
SPOT LOCATION S/2 NW SE
SEC. 21 TWP. 20 RGE. 12 (E) or (W) (W)
COUNTY Barton
Date Well Completed 7-19-57
Plugging Commenced 3-20-85
Plugging Completed 3-5-85

LEASE OPERATOR Four-Way Operating, Inc.

ADDRESS Box 698, Gt. Bend, Ks. 67530

PHONE # (316-792-2506) OPERATORS LICENSE NO. 5310

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filled? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 3480'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	240'	None
				4-1/2"	3480'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Squeezed well with 6 sacks cement thru bradenhead and 30 sacks in 4-1/2" spotted to 330' through 1" tubing. Casing had collapsed on 1", unscrewed one joint and squeezed 4-1/2" with 10 sacks 50/50 pozmix cement with 4% added gel and 3% calcium chloride. Shutin with 500 psi on 4-1/2" casing.

3-14-85

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Great Bend, Ks. 67530

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss. MAR 14 1985

James W. Rockhold (employee of operator) CONSERVATION DIVISION
(operator) of above-described well, being first duly sworn on oath, says: That Wichita, Kansas
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) James W. Rockhold
(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 14th day of March, 1985

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public

My Commission expires: _____

R

~~Barton County~~ DRILLING CONTRACTOR
P. O. BOX 835

~~Poland L. Pettibone, Jr.~~

Phillips # 56

SW NE SE 21-20-12W

Barton County, Kansas

John A. Trimmel NW-SE-SE

Inv. 4043-W

0	-	212	Sand & Shells
212	-	260	Shale & Blue Clay
260	-	622	Shale & Red Bed
622	-	636	Anhydrite
636	-	800	Shale & Shells
800	-	1110	Shale
1110	-	1645	Shale & Lime
1645	-	1895	Lime
1895	-	2895	Lime & Shale
2895	-	2993	Lime
2993	-	3170	Lime & Shale
3170	-	3424	Lime
3424	-		Rotary T.D.

8 5/8" set at 212'.

5 1/2" O.D. set and cemented at 3424'. Cemented with 100 sacks cement.

Dry & Abandoned

RECEIVED
WIRE CORPORATION COLLECTION

DEC 26 1961


CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
COUNTY OF BARTON ss

Virgil E. Belford, Jr., employee of Chas. Hulme Drilling Contractor being first duly sworn on oath says: That I have knowledge of the facts, statement, and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Virgil E. Belford, Jr.
Virgil E. Belford, Jr.

Subscribed and sworn before me this 9th day of December, 1961.



Jean Kemler
Notary Public Barton County

My Commission Expires: 12-3-63

15.009.04923.0000

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ROLAND L. PELT & CO.
Farm- Phillips No. **A3**

SEC. 21 T. 20 R. 12W
C S/2 NE SE
NW

Total Depth. 3480'
Comm. 6-9-57. Comp. 7-19-57
Shot or Treated.
Contractor. Barbour Drlg.
Issued. 2-25-61

County Barton
KANSAS



K. G. S. LIBRARY

CASING:
8" 240'
5" 3480'

Elevation. 1833' RB

Production. 140 BOPD

Figures indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE

TOPS: SCOUT	
Kansas City	3145
Arbuckle	3410
Total Depth	3480

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1985

CONSERVATION DIVISION
Wichita, Kansas