

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Pittsburg Building
Wichita, Kansas

WELL PLUGGING RECORD

Barton County, Sec. 21 Twp. 20 S Rge. 12 (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Herndon Drilling Company

Lease Name Hulme Well No. 1
Office Address 423 Mayo Building, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 12-18 19 53
Application for plugging filed 12-18 19 53
Application for plugging approved 12-18 19 53
Plugging commenced 12-19 19 53
Plugging completed 12-19 19 53

Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Chas. Stough Great Bend, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3513 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled to 250 ft. with Rotary Drilling Mud. Bottom plug was spotted @ 270 ft. with 1/3 sack hulls belog plug and 20 sacks cement was mixed and poured through drill pipe

Hole was filled to 40 ft. base of cellar 1/3 sack of hulls was put in hole and plug on top. 10 sacks of cement mixed and poured through drill pipe

Hole was filled from 250 to 40 and measured by a measuring line

12-29-53

Name of Plugging Contractor Herndon Drilling Company, D
Address Drawer 489, Tulsa, Oklahoma

STATE OF Oklahoma COUNTY OF Tulsa, ss.
Thomas Elliott (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas Elliott

SUBSCRIBED AND SWORN TO before me this 28th day of December, 19 53

My commission expires Sept. 19, 1956 Notary Public.

PLUGGING
FILE SEC 21 Twp. 20 R. 12
BOOK PAGE 3 LINE 6



WELL LOG ON HULME #1

Spudding date: 12/6/53
Date casing set: 12/6/53
Date rotary completed: 12/18/53
Date cable completed:

Location:
Sec. 21-205-12W - Barton Co., Kansas

FROM	TO	FORMATION	REMARKS
0	790	Sand & Shale	Ran 7 Jts. 8-5/8" SW Casing @ 280' Cemented w/ 250 Sx. w/ 200# C.C.
790	1545	Shale & Shells	
1545	1675	Lime	
1675	1865	Sandy Lime	
1865	2585	Lime & Shale	
2585	3513	Lime	
3513		Total Depth	

Well Plugged

Subscribed and sworn to before me this 24th
day of December, 19 53

I certify the above and foregoing to be a true and exact
copy of the original driller's log on the HULME #1

Patsy M. Mearns
Notary Public
My commission expires: 4-22-57

HERNDON DRILLING COMPANY
C. J. Moore
By: _____
Title: Assistant Secretary

PLUGGING
FILE SEC 21 T 20 R 12W
BOX PAGE 3 LINE 6