


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Barton County, Sec. 21 Twp. 20 Rge. 12 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NW/NW/NW
Lease Owner Pauline Byars Oil Production
Lease Name GELWICKS Well No. 4
Office Address Box 836, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ April 14, 19 75
Plugging completed _____ April 25, 19 75
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3455 1/2'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	264	-0-
				5 1/2	3423	746.20'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rigged up jacks and found pipe was parted. Pulled 23 joints.
Ran die-thread nipple on 5 1/2" casing. Screwed in to parted casing and measured in to bridge at 991'. Tried to bail out bridge. Bailed shale at 991'. Ran sand pump but it stopped at 751'. Pulled 24 joints 5 1/2" casing. Plugged well with 4 sacks hulls, 25 sacks gel and 100 sacks 50/50 Pozmix with 4% added gel.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.
Address P. O. Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss. James W. Rockhold (employee of owner) or (owner/lessor) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530 James W. Rockhold (Address)



Subscribed and sworn to before me this 30 day of April, 19 75
Cathy Miller
Notary Public

My commission expires September 30, 1975

RECEIVED
STATE CORPORATION COMMISSION

5-1-75

MAY 1 1975

CONSERVATION DIVISION
Wichita, Kansas

15.009:15560.0000

WELL LOG

COMPANY - CHAS. HULME DRILLING CONTRACTOR

SEC. 21 20S 12W

FARM - GELWICKS WELL No. 4

LOC. NW NW NW

TOTAL DEPTH - 3430'

COMM. - JUNE 7, 1957 COMP. - JUNE 21, 1957

CONTRACTOR - CHAS. HULME DRILLING CONTRACTOR

CASING - 8 5/8" @ 264' w/250 SACKS CEMENT
5 1/2" @ 3423 w/75 SACKS CEMENT

ELEVATION - 1848' RB
PRODUCTION - ARBUCKLE

0	150	SAND
150	264	SAND & SHALE
264	645	RED BED
645	665	ANHYDRITE
665	1500	SHALE & SHELLS
1500	1800	LIME
1800	1925	SHALE & LIME
1925	2135	LIME
2135	2760	SHALE & LIME
2760	2780	LIME
2780	2880	SHALE & LIME
2880	2995	LIME
2995	3075	SHALE & LIME
3075	3155	SHALE & SAND
3155	3430	LIME
3430		R.T.D.

TOPS

ANHYDRITE:	645'
HEEBNER:	3037'
BROWN LIME:	3157'
LANSING:	3172'
CONGLOMERATE:	3410'
ARBUCKLE:	3420'

RECEIVED
STATE CORPORATION COMMISSION

JUL 2 1957

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS }
COUNTY OF BARTON }

ss:

I, C. E. BYARS, of CHAS. HULME DRILLING COMPANY, UPON OATH STATE THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG OF THE GELWICKS #4 WELL.

C. E. BYARS

SUBSCRIBED AND SWORN TO BEFORE ME THIS 8TH DAY OF JULY, 1957

NOTARY PUBLIC

MY COMMISSION EXPIRES: OCTOBER 15, 1957