

15.009.15557.0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_

LEASE NAME Gelwicksa

WELL NUMBER #1

SPOT LOCATION SE NE NW

SEC. 21 TWP. 20 RGE. 12 (E) or (W)

COUNTY Barton

Date Well Completed 4-25-57

Plugging Commenced 2-13-85

Plugging Completed 2-18-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Pauline Byars Oil Production

ADDRESS Box 836, Great Bend, Ks. 67530

PHONE # 792-2506 OPERATORS LICENSE NO. 6596

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3453'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS \_\_\_\_\_ CASING RECORD \_\_\_\_\_

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	215'	None
				5-1/2"	3414'	1,616.89'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped 5 sacks cement on bottom, sanded back to 3360' and dumped 5 sacks cement Shot casing at 3000', 2900', 2700'. Hole bridged at 1780'. Shot casing at 1750' and 1600'. Pulled 50 joints of 5-1/2" casing. Squeezed well with 4 sacks hulls, 10 sacks gel, 40 sacks cement, 5 sacks gel, 1 sack hulls, released plug and pumped 130 sacks 50/50 pozmix cement with 4% added gel and 3% calcuim chloride. Maximum pressure was 200 psi and shutin 50 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111  
Address Box 698, Great Bend, Ks. 67530

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

FEB 20 1985  
2-20-85  
CONSERVATION DIVISION  
Wichita, Kansas

(Signature) James W. Rockhold  
James W. Rockhold  
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 19th day of February, 1985

IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt Exp. 7-26-87

My Commission expires: \_\_\_\_\_

W E L L L O G

Company - Chas. Hulme Drlg. Contr.

Sec. 21 20S 12W

Farm - Gelwicks Well No. 1

Loc. SE NE NW

Total Depth - 3414'

Comm. - March 6, 1957 Comp. - March 21, 1957

Contractor - Chas. Hulme Drlg. Contr.

Casing - 8 5/8" @ 215' w/250 sacks Posmix  
5 1/2" 3414.5' w/75 sacks cement

Elevation - 1848' KB  
Production - Arbuckle

0	200	Clay & Sand
200	215	Shale & Shells
215	635	Red Bed & Shale
635	665	Anhydrite
665	1250	Shale & Shells
1250	1845	Shale & Lime
1845	2100	Lime
2100	2265	Shale & Lime
2265	2540	Shale & Shells
2540	2665	Lime
2665	2765	Shale & Lime
2765	2780	Shale
2780	3045	Lime
3045	3160	Shale
3160	3200	Lime & Shale
3200	3330	Lime
3330	3390	Lime & Shale
3390	3415	Lime
3415		R.T.D.

<u>Tops</u>	
Anhydrite:	635'
Heebner:	3036'
Brown Lime:	3156'
Lansing:	3173'
Conglomerate:	3404'
Arbuckle:	3412'

RECEIVED  
STATE INFORMATION COMMISSION  
FEB 14 1957  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas )  
County of Barton)

ss:

I, C. E. Byars of Chas. Hulme Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Gelwicks #1 well.

C. E. BYARS

Subscribed and sworn to before me this 25th day of March, 1957.

NOTARY PUBLIC

My Commission Expires: October 15, 1957