

RECEIVED
STATE CORPORATION COMMISSION

JUN 06 1983

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

CONSERVATION DIVISION
Wichita, Kansas
WELL PLUGGING RECORD

SE SE NW County, Sec. 21 Twp. 20 Rge. 12 (X) W (W)

Location as "NE/CNWxSWx" or footage from lines 330' FFL & 330' FSL

Lease Owner American Petrofina Co. of Texas

Lease Name Hulme "B" Well No. 1

Office Address 4613 Jacksboro Hwy., Wichita Falls, Tx. 76302

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 1-25 19 57

Application for plugging filed 3-16 19 83

Application for plugging approved (verbal) 5-21 19 83


Plugging commenced 5-21 19 83

Plugging completed 5-25 19 83

Reason for abandonment of well or producing formation Not economical to operate

If a producing well is abandoned, date of last production 6-9 19 67

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Gilber Scheck

Producing formation Lansing-Kansas City Depth to top 3180 Bottom 3400 Total Depth of Well 3505 Feet

Show depth and thickness of all water, oil and gas formations. PBD 3289 1/2

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Water	Surface	230	8-5/8"	230	0
	Oil & Water	Surface	3504	5-1/2"	3504	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

5-21-83 Pumped down 5 1/2" casing with 25 sx regular cement, 4 sx hulls, 10 sx gel, pumped wiper plug and pumped 140 sx regular cement. Pumped 1 sx hulls and 100 sx regular cement down 8-5/8" casing.

5-25-83 Top of cement 405'. Dumped 4 1/2 yds Ready-Mix down casing, filled to surface.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementers
Address Russell Kansas

STATE OF Texas, COUNTY OF Wichita, ss.
R. M. Albers (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) RMA
4613 Jacksboro Hwy., Wichita Falls, Tx. 76302
(Address)

Subscribed and Sworn to before me this 31st day of May, 19 83

My commission expires 6-30-84
Notary Public.

DRILLERS LOG


15.009.04916.0000

Hulme B No. 1
Loc: SE SE NW
Sec: 21-20S-12W
Barton County, Kansas
Company: Honaker-Davis Drilg. Co., et al
Contractor: Honaker-Davis Drilg. Co.

Comm: 1-16-57
Comp: 1-25-57
Rotary Total Depth: 3505'
Casing: 8-5/8" at 230'
5-1/2" at 3505'

0	40	Top Soil & Sand	
40	210	Sand & Gravel	
210	215	Blue Shale	8-5/8" casing cemented
215	230	Blue Shale & Shells	at 230' with 175 sacks
230	625	Red Bed & Shale	cement and 4 sacks
625	655	Anhydrite	calcium chloride.
655	1140	Shale & Shells	
1140	1410	Salt & Shale	
1410	3430	Lime & Shale	
3430	3455	Lime, Shale & Chert	5-1/2" casing cemented
3455	3505	Lime & Shale	at 3505' with 100 sacks
3505		Total Rotary Depth	cement.

I certify that this is the true and correct copy of the above log to the best of my knowledge.


H. S. Forbes

Subscribed and sworn to before me this 29th day of January, 1957.


Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1983

CONSERVATION DIVISION
Wichita, Kansas