


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 N. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 29 Twp. 20S Rge. 12W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW SE NE
Lease Owner Sierra Petroleum Co., Inc.
Lease Name McCULLOUGH A Well No. L
Office Address 420 W. Douglas Ave., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 4/16/57 19
Application for plugging filed 4/15/57 19
Application for plugging approved 4/15/57 19
Plugging commenced 4/16/57 19
Plugging completed 4/16/57 19
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Brundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3495' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	276	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING REPORT:

Filled hole with heavy mud from 3495 up to 240'. Set bridge with 1/3 sacks hulls, wood plug and 20 sks cement through drill pipe up to 200'.
Filled hole with heavy mud from 200 up to 25'. Set bridge w/ 1/3 sks hulls, wood plug and 5 sks cement to cellar 0. Job complete 11:45 a.m. 4/16/57.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address) _____

SUBSCRIBED AND SWORN TO before me this 17th day of April, 19 57

My commission expires 1-30-61.

Margie Cooper
STATE CORPORATION COMMISSION Notary Public.

PLUGGING
FILE SEC. 29 T. 20 R. 12W
BOOK PAGE 7 LINE 2

APR 18 1957 4-18-57
CONSERVATION DIVISION
Wichita, Kansas

SIERRA PETROLEUM CO., INC.

McCULLOUGH A #1

SW SE NE Sec. 29-20S-12W
Barton County, Kansas

Total Depth: 3495'

Elev: 1843 KB

Comm: 4/8/57

Comp: 4/16/57

8 5/8 @ 276' w/375 sks. cement

FORMATION	DEPTH
Sand	192
Shale, Red Bed	276
Red Bed	510
Red Bed & shale	620
Anhydrite	655
Shale & shells	1135
Salt & shale	1260
Shale	1475
Shale & lime	3179
Lime	3255
Lime	3435
Congl.	3464
Arb.	3495

Tops:	DEPTH
Anhydrite	620
Heebner	3054
Brown Lime	3178
Kansas City	3199
Arbuckle	3464

STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Henaker

Subscribed and sworn to before me this 17th day of April, 1957.

Margie Cooper
 Notary Public

My Commission expires: 1-30-61.

RECEIVED
 STATE CORPORATION COMMISSION

APR 18 1957

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 29 T 20 R 12W
 BOOK PAGE 7 LINE 2