


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 29 Twp. 20 Rge. 12 (E) (W) x
Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner E. K. Edmiston
Lease Name Simpson A Well No. #1
Office Address 501 First National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 3-2-64 19
Plugging completed 3-10-64 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation Depth to top Bottom Total Depth of Well 3530' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded off bottom at 3470', mixed and ran 4 sacks cement thru dump bailer.
Bailed hole down, push plug to 240', set 10' rock bridge. Mixed and ran 5 sacks cement thru dump bailer.
Bailed hole to 230', mixed and ran 25 sacks cement with dump bailer.
Mudded hole to 30', mixed and ran 10 sacks cement for top cap.

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of March, 1964

My commission expires 24 October 1964

Sidney D. Miller
Notary Public.

COMPANY

E. K. Edmiston
802 Union National Bldg.
Wichita 2, Kansas

Rotary Drilling Commenced:

July 22, 1960

Rotary Drilling Completed:

August 1, 1960

Well Name:

Simpson "A" #1
SE SE SW 29-20-12W
Barton County, Kns.

Contractor:

E. K. Edmiston Drilling Co., Inc.
802 Union National Bldg.
Wichita, Kansas

Casing record:

279" 8 5/8 w/ 250 sacks
4 1/2" @ 3530' w/ 50 sks cement

LOG

Measurements from top of Rotary Bushing:

Sand and shells	0	-	185
Shale			276
Red Bed and shale			650
Anhydrite			672
Red Bed Shale			875
Shale & shells			1500
Shale & shells			1575
Lime and shale			1700
Lime			1990
Shale & Lime			2450
Shale			2617
Shale & lime			2770
Lime and shale			2895
Lime			2956
Lime & shale			3035
Lime			3090
Lime & shale			3295
Lime			3530 Rotary total depth

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1964

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, E. K. Edmiston, President of the E. K. Edmiston Drilling Company, Inc. hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

E. K. EDMISTON DRILLING CO., INC.

By 
E. K. Edmiston President


STATE OF KANSAS)

) ss

COUNTY OF SEDGWICK)

BE IT REMEMBERED that, on this 28th day of March, 1961, before me, the undersigned, a Notary Public duly commissioned in and for the State and County aforesaid, came E. K. Edmiston, known to me to be the same person who executed the foregoing instrument as President and in behalf of the E. K. Edmiston Drilling Company, Inc. and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.


Frances Marler Notary Public

My commission expires:
June 25, 1964

NOTARY PUBLIC
STATE OF KANSAS
COMMISSION EXPIRES
JUNE 25, 1964