

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20063-00-00

Spot: CSESW

Sec/Twnshp/Rge: 5-20S-20W

660 feet from S Section Line, 1980 feet from W Section Line

Lease/Unit Name: WILLIAMS

Well Number: 2

County: PAWNEE

Total Vertical Depth: 4335 feet

Operator License No.: 5030

Op Name: VESS OIL CORPORATION

Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size

feet:

3140.89

Surface Casing: Size 8.625

feet: 242

WITH 200 SX CMT

Production: Size 5.5

feet: 4324

WITH 175 SX CMT

Liner: Size

feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/06/2002 1:45 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4275' & 5 SX CMT. 1ST PLUG AT 1400' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 60 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/06/2002 4:00 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:


PBTD 4335'. OPEN HOLE 4324-35'. SAND TO 4275' WITH 4 SX CMT. 1ST PLUG AT 630' WITH 60 SX CMT. SHOT CASING AT 630'. DID NOT COME LOOSE. SHOT CASING AT 300'. DID NOT COME LOOSE. 2ND PLUG SHOT CASING AT 200' AND CAME LOOSE. PUMPED 50 SX CMT. PULLED CASING. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
DEC 12 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 200' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED

Form 6223

DATE 12-13-02

INV. NO. 200.306 0937