

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20053-00-00
Spot: CSWSW Sec/Twnshp/Rge: 5-20S-20W
660 feet from S Section Line, 660 feet from W Section Line
Lease/Unit Name: WILLIAMS Well Number: 1
County: PAWNEE Total Vertical Depth: 4350 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: 8/41.38
Surface Casing: Size 8.625 feet: 275 WITH 200 SX CMT
Production: Size 5.5 feet: 4340 WITH 175 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/09/2002 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: CIBP @ 4255' WITH 4 SX CMT. PERFORATE AT 605'. RUN TUBING TO 1400' & PUMP 120 SX CMT & 150# HULLS. CIRCULATE CMT TO SURFACE. PULL TUBING AND PUMP 210 SX CMT. PRESSURE TEST. PUMP 20 SX CMT DOWN BACKSIDE & PRESSURE TEST.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 12/09/2002 4:45 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:


PBTD 4350'. OPEN HOLE 4340-50'. SET CIBP @ 4255' WITH 4 SX CMT. PERFORATE CASING AT 605'. RUN TUBING TO 1400' & PUMP 150# HULLS & 120 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TUBING & PUT SWEDGE ON CASING. PUMPED 210 SX CMT. MAXIMUM PRESSURE 400#. SHUT IN WITH 200#. TIED ONTO BACKSIDE AND PUMPED 20 SX CMT. PRESSURED TO 500# AND HELD.

RECEIVED
DEC 12 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED. HOLES IN CASING.

Plugged through: TBG

District: 01



Signed Michael Maier
(TECHNICIAN)

INVOICED
DATE 12-13-02
INV. NO. 2003060937