

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20201-00-00
Spot: CNWNE Sec/Twnshp/Rge: 5-20S-20W
4620 feet from N Section Line, 1980 feet from E Section Line
Lease/Unit Name: ISAAC Well Number: 4
County: PAWNEE Total Vertical Depth: 4355 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: 8 1/4
Surface Casing: Size 8.625 feet: 278 WITH 150 SX CMT
Production: Size 5.5 feet: 4341 WITH 175 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/28/2003 8:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4290' & 5 SX CMT. PLUG AT 1410' WITH 40 SX CMT. PERFORATE AT 660'. PUMP 140 SX CMT DOWN 5 1/2". PRESSURE TEST. PUMP 35 SX CMT DOWN ANNULUS. PRESSURE TEST.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/28/2003 11:36 AM

KCC Agent: RICHARD LACEY


Actual Plugging Report:

OPEN HOLE AT 4341-55'. SANDED TO 4290' & 5 SX CMT WITH BAILER. SPOTTED PLUG THROUGH TUBING. 1ST PLUG AT 1410' WITH 40 SX COMMON CMT WITH 3% CC. PERFORATED 5 1/2" PIPE AT 660'. PUMPED 140 SX 60/40 POZMIX 6% GEL DOWN 5 1/2" AND OUT AT 660'. NO CIRCULATION. MAXIMUM PRESSURE 500#. SHUT IN AT 450#. PUMPED 35 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 500#. SHUT IN WITH 450#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

FEB 04 2003

KCC WICHITA

INVOICED

DATE 2-5-03

INV. NO. 2003061165

Form CR-7/3