

To: 1 100079
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS-67202

API NUMBER 15- 145-21,443-0000
C SE , SEC. 5 , T 20 S, R 20 WXX
1320 feet from S section line
1320 feet from E section line

11-13
TECHNICIAN'S PLUGGING REPORT
Operator License / 5030
Operator: Vess Oil Corporation
Name & Address: 8100 E. 22nd. St. N, Bldg. 300
Wichita, KS 67226

Lease Name Oliver Well # 5
County Pawnee 141.63
Well Total Depth 4358 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 429

Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated

Plugging Contractor L.D. Drilling, Inc. License Number 6039
Address RR 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: Day: 13 Month: 11 Year: 19 96

Plugging proposal received from Greg Davidson
(company name) L.D. Drilling, Inc. (phone) 316-793-3051
11-15-96

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1393
1st plug at 1350' with 50 sx cement, 2nd plug at 450' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Gary Winters
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: Day: 13 Month: 11 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 1350' with 50 sx cement,
2nd plug at 450' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# flowseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(XXXXX did not) observe this plugging.

DATE NOV 19 1996
INV. NO. 46994

Signed Gary Winters
(TECHNICIAN)

15.145.21443.0000

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

FCS, KCC USE:

EFFECTIVE DATE: 10-28-96

DISTRICT # 1
SEAT... Yes... No

State of Kansas

NOTICE OF INTENTION TO DRILL 145-21,443

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date Nov 15 1996
month day year

Spot G SE/4 Sec 5 Twp 20 S. Rg 20 West

OPERATOR: License # 5030
Name: Vess Oil Corporation
Address: 8100 E. 22nd Street North, Bldg. 300
City/State/Zip: Wichita, KS 67226
Contact Person: W.R. Horgan
Phone: 316-682-1537

1320 feet from South North line of Section
1320 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 6039
Name: L.D. Drilling, Inc.

County: Pawnee
Lease Name: Oliver Well #: 5
Field Name: Schadel South

Is this a Prorated/Spaced Field? ... yes X no
Target Formation(s): Miss

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec X Infield X Mud Rotary
Gas ... Storage ... Pool Ext. ... Air Rotary
OWWO ... Disposal ... Wildcat ... Cable
Seismic; ... # of Holes ... Other

Nearest lease or unit boundary: 1320
Ground Surface Elevation: 2200 feet HSL

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth:
Bottom Hole Location:

Depth to bottom of fresh water: 200
Depth to bottom of usable water: 400
Surface Pipe by Alternate: X 1 2

Exp. 4/23/97

AFFIDAVIT

Length of Surface Pipe Planned to be set: 420
Length of Conductor pipe required:
Projected Total Depth: 4350

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-

Formation at Total Depth: Miss
Water Source for Drilling Operations:
... well ... farm pond X other

DWR Permit #:
Will Cores Be Taken?: ... yes X no
If yes, proposed zone:

420' Alt. I Req.

EW 2200

usher Grey Davidson

PUD DATE 11-5-96 INIT. SO

ENGTH SURFACE PLANNED 420 +

RESERVE PIT STATUS- REMOVE FLUID LINED
fter salt sect. bbls. when done bbls.

ATHOLED AHEAD? Y N SIZE HOLE
URFACE PIPE 8 3/4 @ 4729 CONDUCTOR
NHYDRATE 1393 B- 74 ELEVATION

D 4358 FORMATION MISSISSIPPI

AN PIPE @ DV TOOL ALT II DONE
SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1350 Ft. W/ 50 SX

1/2 Base Anyh. @ Ft. W/ SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ 480 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

WT HOLE CIRC/W 15 SX MOUSE HOLE W/ NO SX

ATER WELL SX (Irr. Well Pond
Hauling

CHNICIAN G.W. DATE 11-13-96

PE OF CEMENT 60/40 Pymate 1/4 Flow Seal

ARTING TIME : (AM/PM) DATE

MPLETION TIME : (AM/PM) DATE

MENT COMPANY Allied (1517)

80 01 01